| DIRECTION | MILEPOINT | LOCATION CODE (SHEET 3) | SIGN CODE | WIDTH (IN) | HEIGHT (IN) | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXIST POST RETAIN | EXIST POST REMOVE | NUMBER OF NEW POSTS | SQUARE STEEL (IN) 1.75 (LB / FT) 1.88 | SQUARE STEEL (IN) 2.00 (LB / FT) 2.42 | SQUARE STEEL (IN) 2.50 (LB / FT) 3.35 | TUBULAR STEEL Ø (IN) FOUNDATION | TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60 | TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00 | TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80 | TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60 | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL LOCATION SHSM | SIGN DETAIL LOCATION PROJECT SHEET # | SIGN DETAIL LOCATION STANDARD SHEET # |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **NB BROOKFIELD VT 12** | | | | | | | FY-FLUORESCENT YELLOW<br>FYG-FLUORESCENT YELLOW GREEN | | | | | | | | | ANCHORS | | | | | | | | | | "SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK | | | |
| NB | 4.572 | A | VD1-1A | 72 | 12 | | ^UP So. Northfield 4 | | | | | | 1 | | X | | | | | | | | | | | | | | |
| | | A | VD1-1A | 72 | 12 | | ^UP Northfield 6 | | | | | | 1 | | | | | | | | | | | | | | | | |
| | | A | VD1-1A | 72 | 12 | | Brookfield 3 ---> | | | | | | 1 | | | | | | | | | | | | | | | | |
| | | A | VD1-1A | 72 | 12 | | Floating Bridge 3 ---> | | | | | | 1 | | | | | | | | | | | | | | | | |
| | | A | VD-700 | 6 | 8 | | MILE MARKER 0120 / 0903 / 0460 | | | | | | 1 | | | | | | | | | | | | | | | | |
| | | A | VD1-1A | 72 | 12 | | S Northfield 4 | 6.00 | | | | | | | | 8'<br>2 | | | 11'-5"<br>12'-1"<br>X | | | | | | | SLIP BASE REQUIRED<br>SEE SHEET 3 | | 8 | |
| | | A | VD1-1A | 72 | 12 | | Northfield 7 | 6.00 | | | | | | | | | | | | | | | | | | | | 8 | |
| | | A | VD1-1A | 72 | 12 | | Brookfield 3 → | 6.00 | | | | | | | | | | | | | | | | | | | | 8 | |
| | | A | VD1-1A | 72 | 12 | | Floating Bridge 3 → | 6.00 | | | | | | | | | | | | | | | | | | | | 8 | |
| NB | 4.595 | A | M3-1 | 24 | 12 | | NORTH | | | | | | 1 | | X | | | | | | | | | | | | | | |
| | | A | VM1-5 | 24 | 24 | | VERMONT 12 | | | | | | 1 | | | | | | | | | | | | | | | | |
| | | A | M6-3 | 21 | 15 | | ^UP ARROW | | | | | | 1 | | | | | | | | | | | | | | | | |
| | | A | M3-2 | 24 | 12 | | EAST | | | | | | 1 | | | | | | | | | | | | | | | | |
| | | A | VM1-5 | 24 | 24 | | VERMONT 65 | | | | | | 1 | | | | | | | | | | | | | | | | |
| | | A | M6-1R | 21 | 15 | | RIGHT ---> | | | | | | 1 | | | | | | | | | | | | | | | | |
| **SIGN SUMMARY SHEET** | | | | | | | SHEET TOTALS | 24.00 | 0.00 | 0 | 0 | 0 | 11 | 0 | 0 | 2 | | | 31'-6"<br>~~30.0~~ | 0 | 0.0 | 0.0 | 0.0 | 0.0 | | | | | |
| | | | | | | | | SF | SF | EA | EA | EA | EA | EA | EA | EA | | | FT | EA | LB | LB | LB | LB | | | | | |
| VERMONT AGENCY OF TRANSPORTATION | | | | | | | TOWN DIRECTIONAL TOTALS | 255.7 | 0.0 | 1 | 0 | 0 | 45 | 0 | 0 | 50 | | | 715.0 | 0 | | | 0.0 | | | | | |

PROJECT NAME: **RANDOLPH-BERLIN**
PROJECT NUMBER: **STPG SIGN(52)**
FILE NAME: **z13c626tssbrookfield NB** PLOT DATE: **5/12/2015**
PROJECT MANAGER: **C. BEAN** DRAWN BY: **S. GOODWIN**
DESIGNED BY: **S. GOODWIN** CHECKED **D. MUNRO**
BROOKFIELD VT-12 NORTHBOUND 5 SHEET **35** OF **105**