DIRECTION	MILEPOINT	LOCATION CODE (SHEET 3)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
NB BROOKFIELD VT 12							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN									ANCHORS										"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
NB	5.160	A	W1-10	30	30		MODIFIED LEFT CURVE						1		X														
		A	W13-1P	18	18		40 MPH						1																
		A	VD-700	6	8		MILE MARKER 0120 / 0903 / 0518						1																
NB	5.210	A	W1-10cL	36	36			9.00								8′ 2	11′-8" 11′-6" X										X		
		A	W13-1P	18	18			2.25																		INSTALL ON LEFT POST	X		
NB	5.275	AB	D-3	18	6		HOWE RD						1		X											HOWE RD (TH-24)			
		AB	D3-1	39	12			3.25								4′ 1	6′-6" X									INSTALL INDEPENDENTLY ON ONE POST ON THE LEGAL LOAD SIDE OF THE INTERSECTION		10	
NB	5.276	C	W1-6R	48	24								1		X											SIGN FACING SOUTHBOUND TRAFFIC			
		C	W1-6R	48	24			8.00								8′ 2	7′-7" 8′-1" X										X		
NB	5.277	C	VR-017	24	30								1		X											HOWE RD (TH-24)			
		C	VR-017	24	30			5.00								4′ 1	8′-7" X									INSTALL NEW SIGN AT SAME LOCATION ON HOWE RD			E-141
NB	5.288	D	R1-1	30	30								1		X														
		D	R1-1	30	30			6.25								4′ 1	8′-10" X										X		
NB	5.290	A	W1-6L	48	24								1		X														
		A	W1-6L	48	24			8.00								8′ 2	8′-0" 8′-0" X									ENSTURE VISIBILITY IS NOT BLOCKED BY STOP SIGN	X		
SIGN SUMMARY SHEET							SHEET TOTALS	41.75	0.00	0	0	0	8	0	0	9	~~114′-9"~~ 135.0			0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT			EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	~~272.68~~ 255.7	0.0	1	0	0	~~49~~ 45	0	0	~~49~~ 50	~~646.08~~ 715.0			0	0.0								

PROJECT NAME: **RANDOLPH-BERLIN**
PROJECT NUMBER: **STPG SIGN(52)**

FILE NAME: **z13c626tssbrookfield NB** PLOT DATE: **5/12/2015**
PROJECT MANAGER: **C. BEAN** DRAWN BY: **S. GOODWIN**
DESIGNED BY: **S. GOODWIN** CHECKED **D. MUNRO**
BROOKFIELD VT-12 NORTHBOUND 8 SHEET **38** OF **105**