DIRECTION	MILEPOINT	LOCATION CODE (SHEET 3)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SB BROOKFIELD VT 12							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN									ANCHORS										"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
SB	4.532	F	M3-3	24	12		SOUTH						1		X														
		F	VM1-5	24	24		VERMONT 12						1																
SB	4.482	F	W1-5L	36	36		LEFT WINDING CURVES						1		X														
		F	W7-3aP	36	24		NEXT 4 MILES						1																
		F	W1-5RL	30	30	FY		6.25								4′ 1		12′-7" X								TYPE IX FLUORESCENT YELLOW SHEETING	X		
		F	W7-3aP	24	18	FY		3.00																		TYPE IX FLUORESCENT YELLOW SHEETING	X		
SB	3.958	F	W1-2L	30	30	FY		6.25								4′ 1		11′-11" X								TYPE IX FLUORESCENT YELLOW SHEETING	X		
		F	W13-1P	18	18	FY		2.25																		TYPE IX FLUORESCENT YELLOW SHEETING	X		
SB	3.674	F	W1-4L	30	30	FY		6.25								4′ 1		12′-9" X								TYPE IX FLUORESCENT YELLOW SHEETING	X		
		F	W13-1P	18	18	FY		2.25																		TYPE IX FLUORESCENT YELLOW SHEETING	X		
SB	3.617	F	W1-6L	48	24	FY		8.00								8′ 2		8′-11" 8′-8" X								TYPE IX FLUORESCENT YELLOW SHEETING	X		
SB	3.610	E	W1-6R	48	24	FY		8.00								8′ 2		9′-3" 8′-10" X								INSTALL SIGN FACING NORTHBOUND TRAFFIC. TYPE IX FLUORESCENT YELLOW SHEETING.	X		
SB	3.589 - 3.371	F	N/A	6	8		INSTALL (13) NEW DELINEATOR POSTS																			INSTALL (26) TYPE II 6"x8" WHITE DELINEATORS BACK TO BACK ON 13 NEW POSTS; INSTALL THE FIRST POST 110 FT ± SOUTH OF PROPOSED SIGN AT 3.610, THEN EVERY 100 FT ±		5	
SIGN SUMMARY SHEET							SHEET TOTALS	42.25	0.00	0	0	0	4	0	0	7		100′-11" ~~105.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	232.3	0.0	4	1	1	44	0	0	43		615.0		0	0.0								

PROJECT NAME: **RANDOLPH-BERLIN**
PROJECT NUMBER: **STPG SIGN(52)**

FILE NAME: **z13c626tssbrookfield SB** PLOT DATE: **5/12/2015**
PROJECT MANAGER: **C. BEAN** DRAWN BY: **S. GOODWIN**
DESIGNED BY: **S. GOODWIN** CHECKED **D. MUNRO**
BROOKFIELD VT-12 SOUTHBOUND 5 SHEET **43** OF **105**