DIRECTION	MILEPOINT	LOCATION CODE (SHEET 3)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
NB ROXBURY VT12							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN									ANCHORS										"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
NB	0.000	C	VD-024	60	7.5		ROXBURY / BROOKFIELD						1		X													
		C	VD-025	60	7.5		WASHINGTON CO. / ORANGE CO.						1															
		C	VD-700	6	10		MILE MARKER 0120 / 1215 / 0000 (ROXBURY)				1		1															
		C	VD-700	6	10		MILE MARKER 0120 / 0903 / 0552 (BROOKFIELD)				1		1															
		C	VD-024	72	10		Roxbury | Brookfield	5.00								8′ 2		9′-10" 9′-7" X								INSTALL THIS ASSEMBLY CENTERED IN THE SAME POSITION AS THE REMOVAL		9	
		C	VD-025	72	10		Washington Co. | Orange Co.	5.00																				9	
		C	VD-700	6	10		MILE MARKER 0120 / 1215 / 0000 (ROXBURY)					1														INSTALL ROXBURY MILE MARKER ON LEFT POST UNDER ROXBURY			
		C	VD-700	6	10		MILE MARKER 0120 / 0903 / 0552 (BROOKFIELD)					1														INSTALL BROOKFIELD MILE MARKER ON RIGHT POST UNDER BROOKFIELD			
NB	0.050	AB	D-3	18	6		HERRIOTT RD						1		X													
		AB	D3-1	42	12		Herriott Rd	3.50								4′ 1		7′-0" X								INSTALL AT SAME LOCATION AS EXISTING SIGN		10	
NB	0.120 ~~0.192~~	A	W1-10R	36	36			9.00								8′ 2		9′-6" 10′-3" X								CURVE ADEQUATE FOR 45 MPH. INSTALL 75 FT ± SOUTH OF EXISTING SIGN AT MP 0.206.	X		
		A	W16-8P	33	8			1.83																				7	
NB	0.206	A	W1-10	30	30		MODIFIED RIGHT CURVE						1		X													
		A	W13-1P	18	18		35 M.P.H. (PLAQUE)						1															
NB		A	S3-I	36	36	FYG		9.00								8′ 2		7′-7" 10′-3" X											
SIGN SUMMARY SHEET							SHEET TOTALS	~~33.33~~ ~~24.33~~	0.00	0	2	2	7	0	0	~~7~~ ~~5~~		~~92′-0"~~ ~~75.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	44.6	0.0	0	2	2	9	0	0	9		135.0		0	0.0								

PROJECT NAME: **RANDOLPH-BERLIN**
PROJECT NUMBER: **STPG SIGN(52)**

FILE NAME: **z13c626tssroxburv NB**
PROJECT MANAGER: **C. BEAN**
DESIGNED BY: **S. GOODWIN**
ROXBURY VT-12 NORTHBOUND 1

PLOT DATE: **5/12/2015**
DRAWN BY: **S. GOODWIN**
CHECKED **D. MUNRO**
SHEET **47** OF **105**