DIRECTION	MILEPOINT	LOCATION CODE (SHEET 3)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
NB NORTHFIELD VT 12							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN									ANCHORS										"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
NB	0.000	C	VD-024	60	7.5		NORTHFIELD / ROXBURY						1		X														
		C	VD-700	6	10		MILE MARKER 0121 / 1215 / 0148 (ROXBURY)						1																	
		C	VD-700	6	8		MILE MARKER 0120 / 1213 / 0000 (NORTHFIELD)						1																	
		C	VD-024	72	10		Northfield | Roxbury	5.00								8′ 2		6′-11" 7′-0" X								INSTALL THIS ASSEMBLY CENTERED IN THE SAME POSITION AS THE REMOVAL		9	
		C	VD-700	6	10		0120 1213 0000 / 0120 1215 0148	0.42																		INSTALL NORTHFIELD MILE MARKER ON LEFT POST UNDER NORTHFIELD			T-44
		C	VD-700	6	10			0.42																		INSTALL ROXBURY MILE MARKER ON RIGHT POST UNDER ROXBURY			T-44
NB	0.531	A	W1-2R	30	30		RIGHT CURVE						1		X														
		A	W13-1P	18	18		30 MPH						1																
		A	W1-5R	36	36			9.00								8′ 2		8′-11" 8′-11" X										X	
		A	W13-1P	18	18			2.25																		INSTALL ON LEFT POST		X	
		A	W7-3aP	24	18		35 MPH / NEXT 1 MILE	3.00																		INSTALL ON RIGHT POST		X	
NB	0.616	A	OM3-R	12	36								1		X														
		A	OM3-R	12	36			3.00								4′ 1		6′-10" X								INSTALL AT 4 FT VERTICAL CLEARANCE THINNING AND TRIMMING		X	
NB	0.716	A	VD-701	6	8		BRIDGE 56 VT-12						1		X														
		A	VD-701	6	10			0.42								4′ 1	4′-10" X												T-42
							SHEET TOTALS	23.51	0.00	0	0	0	7	0	0	6		6′-5" ~~85.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	439.4	0.0	27	0	0	95	0	0	79		1160.0		0		0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **RANDOLPH-BERLIN**
PROJECT NUMBER: **STPG SIGN(52)**

FILE NAME: **z13c626tssnorthfield NB**
PROJECT MANAGER: **C. BEAN**
DESIGNED BY: **S. GOODWIN**
NORTHFIELD VT-12 NORTHBOUND 1

PLOT DATE: **5/12/2015**
DRAWN BY: **S. GOODWIN**
CHECKED **D. MUNRO**
SHEET **53** OF **105**