DIRECTION	MILEPOINT	LOCATION CODE (SHEET 3)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
NB NORTHFIELD VT 12							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN									ANCHORS										"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
NB	5.200	C	R2-1	18	24		SPEED LIMIT 25						1		X											DOYON RD (TH-16)			
		C	VR-017	24	30		LLL 24,000 LBS						1																
		C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								4′ 1		12′-7" X								INSTALL NEW SIGN AT SAME LOCATION ON DOYON RD			E-141
		C	R2-1	24	30		SPEED LIMIT 25	5.00																			X		
NB	5.207	AB	D-3	18	9		DOYON RD						1		X														
		D	R1-1	30	30		STOP						1																
		AB	D3-1	42	12		Doyon Rd	3.50								4′ 1		9′-8" X								INSTALL PERPENDICULAR ON TOP OF STOP SIGN		10	
		D	R1-1	30	30		STOP	6.25																			X		
		C	VD-700	6	10		0120 1213 0520	0.42																		INSTALL BACK TO BACK ON STOP SIGN POST			T-44
NB	5.444	A	VD-018	30	18		NORTHFIELD FALLS RIVERTON 2						1		X														
		A	VD-018	30	18		Northfield Falls Riverton 2	3.75								4′ 1		10′-5" X										9	
NB	5.579	A	R2-1	24	30		SPEED LIMIT 35						1		X														
		A	R2-1	24	30			5.00								4′ 1		8′-10" X										X		
NB	5.635	A	VW-060	30	30		HIDDEN DRIVES						1		X														
		A	VW-054	30	30		HIDDEN DRIVES RIGHT	6.25								4′ 1		9′-7" X												E-154
SIGN SUMMARY SHEET							SHEET TOTALS	35.17	0.00	0	0	0	7	0	0	5		71′-1" ~~75.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	439.4	0.0	27	0	0	95	0	0	79		1160.0		0	0.0								

PROJECT NAME: **RANDOLPH-BERLIN**
PROJECT NUMBER: **STPG SIGN(52)**

FILE NAME: **z13c626tssnorthfield NB**
PROJECT MANAGER: **C. BEAN**
DESIGNED BY: **S. GOODWIN**
PLOT DATE: **5/12/2015**
DRAWN BY: **S. GOODWIN**
CHECKED **D. MUNRO**

NORTHFIELD VT-12 NORTHBOUND 10

SHEET **62** OF **105**