DIRECTION	MILEPOINT	LOCATION CODE (SHEET 3)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
NB NORTHFIELD VT 12							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN									ANCHORS										"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
		D	R4-7	24	30		(CONT.)	5.00																			X		
NB	5.791	B	R5-1	30	30								1		X												DAVIS AVE (TH-16)			
		B	R5-1	30	30			6.25								4′ 1		9′-5" X								INSTALL AT SAME LOCATION IN ISLAND FACING VT ROUTE 12 SOUTHBOUND TRAFFIC			
NB	5.795	D	R1-1	30	30		STOP						1		X														
		C	R5-1	30	30		DO NOT ENTER						1														ON BACK			
		C	VD-700	6	8		MILE MARKER 0120 / 1213 / 0580						1																	
		D	R1-1	30	30			6.25								4′ 1		9′-4" X									X		
		C	R5-1	30	30			6.25																		INSTALL BACK TO BACK ON STOP SIGN POST	X		
		C	VD-700	6	10		0120 1213 0580	0.42																		INSTALL BACK TO BACK ON STOP SIGN POST			T-44
NB	5.807	A	VW1-2M	30	30		MODIFIED RIGHT CURVE						1		X														
		A	W1-10a	36	36			9.00								8′ 2		10′-9" 10′-8" X									X		
		A	W16-8aP	48	15		Gould Rd Cox Brook Rd	5.00																				7	
NB	5.864	A	R2-1	24	30		SPEED LIMIT 25						1		X												GOULD RD (TH-17)			
		C	VR-017	24	30		LLL 24,000 LBS						1																
		C		18	24		NEIGHBORHOOD WATCH SIGN (CONT. ON NEXT SHEET)						1														RETURN TO TOWN			
							SHEET TOTALS	38.17	0.00	0	0	0	8	0	0	4		56′-2" ~~60.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	439.4	0.0	27	0	0	95	0	0	79		1160.0		0		0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **RANDOLPH-BERLIN**
PROJECT NUMBER: **STPG SIGN(52)**

FILE NAME: **z13c626tssnorthfield NB** PLOT DATE: **5/12/2015**
PROJECT MANAGER: **C. BEAN** DRAWN BY: **S. GOODWIN**
DESIGNED BY: **S. GOODWIN** CHECKED **D. MUNRO**
NORTHFIELD VT-12 NORTHBOUND 12 SHEET **64** OF **105**