DIRECTION	MILEPOINT	LOCATION CODE (SHEET 3)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SB NORTHFIELD VT 12							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN									ANCHORS										"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
SB	5.906	H	R1-1	30	30								1		X														
		G	VD-700	6	8		MILE MARKER 0120 / 1213 / 0591						1																
		H	R1-1	30	30			6.25								4′ 1		9′-6" X										X		
		G	VD-700	6	10			0.42																			INSTALL BACK TO BACK ON STOP SIGN POST			T-44
SB	5.881	F	W11-2	30	30								1		X														
		F	W16-7P	24	12								1																
		F	W11-2	30	30	FYG		6.25								4′ 1		10′-2" X										X		
		F	W16-7P	24	12	FYG		2.00																				X		
SB	5.881	F		12	18		BUS STOP			1				X															
SB	5.879	EF	D-3	9	24		COX BROOK RD						1		X												COX BROOK RD (TH-3)			
		G	VR-004A	24	30		YIELD TO PEDESTRIAN SIGN						1																
		EF	D3-1	57	12		Cox Brook Rd BUS STOP R&S	4.75			I	I	I			8′ 2		7′-2" 7′-0" X								INSTALL INDEPENDENTLY ON TWO POSTS ON LEGAL LOAD SIDE OF INTERSECTION		10	
SB	5.878	G	VR-017	24	30		LEGAL LOAD LIMIT 20,000 POUNDS						1		X														
		G	VR-017	24	30			5.00								4′ 1		10′-3" X									INSTALL NEW SIGN AT SAME LOCATION ON COX BROOK RD			E-141
SIGN SUMMARY SHEET							SHEET TOTALS	24.67	0.00	1	~~0~~ I	~~0~~ I	~~7~~ 8	0	0	5		~~75.0~~ 64′-1"		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	341.2	0.0	26	2	2	72	0	0	65		950.0		0	0.0								

PROJECT NAME: **RANDOLPH-BERLIN**
PROJECT NUMBER: **STPG SIGN(52)**

FILE NAME: **z13c626tssnorthfield SB**
PROJECT MANAGER: **C. BEAN**
DESIGNED BY: **S. GOODWIN**
NORTHFIELD VT-12 SOUTHBOUND 3

PLOT DATE: **5/12/2015**
DRAWN BY: **S. GOODWIN**
CHECKED **D. MUNRO**
SHEET **70** OF **105**