DIRECTION	MILEPOINT	LOCATION CODE (SHEET 3)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SB NORTHFIELD VT 12							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN									ANCHORS										"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
SB	2.731	EF	D-3	24	9		TERRACE DR						1		X													
		H	R1-1	30	30		STOP SIGN						1															
		G	VD-700	6	8		MILE MARKER 0120 / 1213 / 0274						1															
		EF	D3-1	42	12			3.50								4′ 1		9′-6" X							INSTALL PERPENDICULAR ON TOP OF STOP SIGN		10	
		H	R1-1	30	30			6.25																			X		
		G	VD-700	6	10			0.42																			INSTALL BACK TO BACK ON STOP SIGN POST			T-44
SB	2.728	F	W11-6H	30	30								1		X												FOLDING / HINGED			
		F	W11-6H	30	30			6.25								4′ 1		10′-0" X											E-153
SB	2.610	F	R2-1	24	30		SPEED LIMIT 40						1		X												REMOVE. SEE MP 3.044 & 2.425			
SB	2.518	G	VR-017	24	30		LLL 24,000 LBS						1		X												PRESTON DR (TH-107)			
		G	W14-1	24	24		DEAD END						1																
		G	W14-1	30	30			6.25								4′ 1		10′-9" X							INSTALL AT SAME LOCATION AS EXISTING DEAD END SIGN	X		
SB	2.518	G	VR-017	24	30			5.00								4′ 1		9′-4" X							INSTALL ON LEGAL LOAD SIDE OF THE TOWN HIGHWAY. INSTALL ACROSS FROM EXISTING STOP SIGN.			E-141
SB	2.513	EF	D-3	30	9		PRESTON DR						1		X														
		H	R1-1	30	30		STOP SIGN (CONT. ON NEXT SHEET)						1																	
SIGN SUMMARY SHEET							SHEET TOTALS	27.67	0.00	0	0	0	9	0	0	4		55′-7" ~~60.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	341.2	0.0	26	2	2	72	0	0	65		950.0		0	0.0								

PROJECT NAME: **RANDOLPH-BERLIN**
PROJECT NUMBER: **STPG SIGN(52)**

FILE NAME: **z13c626tssnorthfield SB** PLOT DATE: **5/12/2015**
PROJECT MANAGER: **C. BEAN** DRAWN BY: **S. GOODWIN**
DESIGNED BY: **S. GOODWIN** CHECKED **D. MUNRO**
NORTHFIELD VT-12 SOUTHBOUND 7 SHEET **74** OF **105**