DIRECTION	MILEPOINT	LOCATION CODE (SHEET 3)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SB NORTHFIELD VT 12							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN									ANCHORS										"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
		G	VD-700	6	8		MILE MARKER 0120 / 1213 / 0252 (CONT.)						1																
		EF	D3-1	42	12		Preston Dr / STOP / 0120 1213 0252	3.50								4′ 1		10′-6" X								INSTALL PERPENDICULAR ON TOP OF STOP SIGN		10	
		H	R1-1	30	30			6.25																			X		
		G	VD-700	6	10			0.42																		INSTALL BACK TO BACK ON STOP SIGN POST			T-44
SB	2.425	F	R2-1	24	30		SPEED LIMIT 40						1		X														
		F	R2-1	24	30			5.00								4′ 1		10′-6" X									X		
SB	2.155	F	M2-1	21	15		JCT			1				X															
		F	VM1-5	24	24		VERMONT 64			1																			
SB	2.114	F	D1-1a	72	12		^UP E. Braintree 10			1				X															
		F	D1-1a	72	12		^UP Randolph 14			1																			
		F	D1-1a	72	12		<--- Williamstown 7			1																			
SB	2.072	F	VR-922L	36	30		LEFT "ONLY"/THRU & RIGHT			1				X															
SB	2.049	F	M3-2	24	12		EAST			1				X															
		F	VM1-5	24	24		VERMONT 64			1																			
		F	M6-1	21	15		<--- LEFT (CONT. ON NEXT SHEET)			1																			
SIGN SUMMARY SHEET							SHEET TOTALS	15.17	0.00	9	0	0	2	0	0	2		~~30.0~~ 29′-0"		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	341.2	0.0	26	2	2	72	0	0	65		950.0		0		0.0							

PROJECT NAME: **RANDOLPH-BERLIN**
PROJECT NUMBER: **STPG SIGN(52)**
FILE NAME: **z13c626tssnorthfield SB**
PROJECT MANAGER: **C. BEAN**
DESIGNED BY: **S. GOODWIN**
NORTHFIELD VT-12 SOUTHBOUND 8
PLOT DATE: **5/12/2015**
DRAWN BY: **S. GOODWIN**
CHECKED **D. MUNRO**
SHEET **75** OF **105**