DIRECTION	MILEPOINT	LOCATION CODE (SHEET 3)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
NB BERLIN VT12							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN									ANCHORS										"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
NB	0.000	C	VD-024	60	7.5		BERLIN / NORTHFIELD						1		X														
		C	VD-700	6	8		MILE MARKER 0120 / 1203 / 0000 (BERLIN)						1																	
		C	VD-700	6	8		MILE MARKER 0120 / 1213 / 0626 (NORTHFIELD)						1																	
		C	VD-024	72	10		Berlin | Northfield	5.00								8′ 2		7′-10" 7′-10" X								INSTALL THIS ASSEMBLY CENTERED IN THE SAME POSITION AS THE REMOVAL		9	
		C	VD-700	6	10		0120 1203 0000 / 0120 1213 0626	0.42																		INSTALL BERLIN MILE MARKER ON LEFT POST UNDER BERLIN			T-44
		C	VD-700	6	10			0.42																		INSTALL NORTHFIELD MILE MARKER ON RIGHT POST UNDER NORTHFIELD			T-44
NB	0.777	AB	D-3	24	6		DARLING RD						1		X														
NB	0.777	C	W14-1	30	30		DEAD END						1														ON TREE			
NB	0.777	C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								4′ 1		11′-10" X								INSTALL AT SAME LOCATION OF EXISTING DEAD END SIGN IN FRONT OF TREE			E-141
		C	R2-1	24	30		SPEED LIMIT 25	5.00																			X		
NB	0.777	C	W14-2	30	30		NO OUTLET	6.25								4′ 1		10′-0" X								INSTALL 50 FT ± UP DARLING RD FROM PROPOSED LLL / SL25 SIGN ASSEMBLY	X		
NB	0.777	C	R2-1	24	30		SPEED LIMIT 25						1		X														
		C	VR-017	24	30		LLL 24,000 LBS						1																	
NB	0.788	D	R1-1	30	30		STOP						1		X														
		C	VD-700	6	8		MILE MARKER 0120 / 1203 / 0079 (CONT. ON NEXT SHEET)						1																	
							SHEET TOTALS	22.09	0.00	0	0	0	9	0	0	4		~~60.0~~ 53′-6"		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	399.8	0.0	8	3	3	83	0	0	96		1385.0		0			0.0						

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **RANDOLPH-BERLIN**
PROJECT NUMBER: **STPG SIGN(52)**
FILE NAME: **z13c626tssberlin NB**
PROJECT MANAGER: **C. BEAN**
DESIGNED BY: **S. GOODWIN**
PLOT DATE: **5/12/2015**
DRAWN BY: **S. GOODWIN**
CHECKED **D. MUNRO**