

# QUANTITY SHEET 2

STATE OF VERMONT  
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	RAILROAD - BID ITEMS	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							1				1		LS	TRAFFIC CONTROL (STP 2956(I))	641J0	-			
							2				2		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641J5	-			
							16700				16700		LF	4 INCH WHITE LINE, LOW VOC CHLORINATED RUBBER PAINT	646.202	13			
							12600				12600		LF	4 INCH YELLOW LINE, LOW VOC CHLORINATED RUBBER PAINT	646.212	47			
							3800				3800		LF	6 INCH WHITE LINE, LOW VOC CHLORINATED RUBBER PAINT	646.2142	66			
							1600				1600		LF	8 INCH WHITE LINE, LOW VOC CHLORINATED RUBBER PAINT	646.222	81			
							600				600		LF	8 INCH YELLOW LINE, LOW VOC CHLORINATED RUBBER PAINT	646.232	48			
							400				400		LF	24 INCH STOP BAR, LOW VOC CHLORINATED RUBBER PAINT	646.262	32			
							110				110		EACH	LETTER OR SYMBOL, LOW VOC CHLORINATED RUBBER PAINT	646.302	-			
							1050				1050		LF	CROSSWALK MARKING, LOW VOC CHLORINATED RUBBER PAINT	646.312	29			
							2				2		EACH	RAILROAD CROSSING SYMBOL, LOW VOC CHLORINATED RUBBER PAINT	646.322	-			
							33400				33400		LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	26			
							25200				25200		LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	94			
							7500				7500		LF	TEMPORARY 6 INCH WHITE LINE, PAINT	646.622	32			
							800				800		LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	64			
							164				164		EACH	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-			
							2100				2100		LF	TEMPORARY CROSSWALK MARKING, PAINT	646.702	58			
							4				4		EACH	TEMPORARY RAILROAD CROSSING SYMBOL, PAINT	646.712	-			
							3000				3000		EACH	LINE STRIPING TARGETS	646.76	61			
							75				75		LF	PAINTED CURB	646.81	4			
							100				100		LB	SEED	651J5	EST.			
							500				500		LB	FERTILIZER	651J8	EST.			
							2				2		TON	AGRICULTURAL LIMESTONE	651.20	EST.			
							2				2		TON	HAY MULCH	651.25	EST.			
							50				50		CY	TOPSOIL	651.35	EST.			
							755				755		SF	TRAFFIC SIGNS, TYPE A	675.20	0.6			
							150				150		LB	TUBULAR STEEL SIGN POST	675.33	10			
							1180				1180		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	4			
							1				1		EACH	FOUNDATION FOR TUBULAR STEEL POST	675.43	-			
							210				210		EACH	REMOVING SIGNS	675.50	-			
							15				15		EACH	ERECTING SALVAGED SIGNS	675.60	-			
							5				5		EACH	SETTING SALVAGED POSTS	675.61	-			
							1				1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.J.)	690.50	-			
							10				10		EACH	SPECIAL PROVISION (CPM SCHEDULE)	900.620	-			
							1				1		EACH	SPECIAL PROVISION (MODIFY EXISTING PEDESTRIAN SIGNAL SYSTEM, INTERSECTION) (VT RT 2A @ TH 5)	900.620	-			
							1				1		EACH	SPECIAL PROVISION (MODIFY EXISTING PEDESTRIAN SIGNAL SYSTEM, INTERSECTION)(VT RT 2A @ TH 450)	900.620	-			
							1				1		EACH	SPECIAL PROVISION (VEHICLE STOP BAR DETECTION SYSTEM)(VT RT 2A @ TH 450)	900.620	-			
							1				1		EACH	SPECIAL PROVISION (VEHICLE STOP BAR DETECTION SYSTEM)(VT RT 2A @ TH 5)	900.620	-			
								170			170		LF	SPECIAL PROVISION (BAND JOINT @ PRECAST CONCRETE RAILROAD CROSSING)	900.640	2			
							100				100		SF	SPECIAL PROVISION (TRAFFIC SIGNS, EXTRUDED)	900.670	0.7			

Sheet has not been updated.  
See SiteManager for quantities  
utilized on this project.



PROJECT NAME: ESSEX JUNCTION	
PROJECT NUMBER: STP 2956(I)	
FILE NAME: z14v25lqty.dgn	PLOT DATE: 4/19/2016
PROJECT LEADER: D.GOZALKOWSKI	DRAWN BY: A. KIRBY
DESIGNED BY: J. OLSEN	CHECKED BY: J. SHIELDS
QUANTITY SHEET 2	SHEET 22 OF 171