STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 9

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	SEE NOTE 2	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.8 (1.88)	2.0 (2.42)	2.5 (3.35)	ANCHOR	SLEEVE	TUBULAR STEEL Ø (in) FOUND-ATION	3.0 (7.6)	3.5 (9.0)	4.0 (10.8)	5.0 (14.6)	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS SHSM = FHWA STANDARD HIGHWAY SIGNS AND MARKINGS BOOK	SIGN DETAIL DETAIL IN SHSM	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
ESSEX JUNCTION VT ROUTE 2A PA 35+45.0, LT	EAST EAST	1 1	24 24	12 12	2.00 2.00				1																					*2B	SIGN ID CODE M3-2, GREEN ON WHITE SIGN ID CODE M3-2, GREEN ON WHITE			E-136B E-136B
	VERMONT 15 VERMONT 117	1 1	24 30	24 24	4.00 5.00																										SIGN ID CODE MI-5, GREEN ON WHITE SIGN ID CODE MI-5, GREEN ON WHITE			E-136B E-136B
		1 1	21 21	15 15	2.19 2.19																										GREEN ON WHITE SIGN ID CODE M6-3, GREEN ON WHITE	M5-2		E-136B
	NORTH SOUTH	1 1	24 24	12 12	2.00 2.00																									*2A	SIGN ID CODE M3-1, GREEN ON WHITE SIGN ID CODE M3-3, GREEN ON WHITE			E-136B E-136B
	VERMONT 2A VERMONT 2A	1 1	24 24	24 24	4.00 4.00																										SIGN ID CODE MI-5, GREEN ON WHITE SIGN ID CODE MI-5, GREEN ON WHITE			E-136B E-136B
		1 1	21 21	15 15	2.19 2.19																										SIGN ID CODE M6-1L, GREEN ON WHITE SIGN ID CODE M6-1, GREEN ON WHITE SIGNS TO BE MOUNTED TO EXISTING POST			E-136B E-136B
PA 35+45.0, RT	NORTH EAST	1 1	24 24	12 12	2.00 2.00				1																					*2A	SIGN ID CODE M3-1, GREEN ON WHITE SIGN ID CODE M3-2, GREEN ON WHITE			E-136B E-136B
	VERMONT 2A VERMONT 15	1 1	24 24	24 24	4.00 4.00																										SIGN ID CODE MI-5, GREEN ON WHITE SIGN ID CODE MI-5, GREEN ON WHITE			E-136B E-136B
		1 1	21 21	15 15	2.19 2.19																										SIGN ID CODE M6-3, GREEN ON WHITE GREEN ON WHITE	M5-2R		E-136B
	WEST EAST	1 1	24 24	12 12	2.00 2.00																									*2B	SIGN ID CODE M3-4, GREEN ON WHITE SIGN ID CODE M3-2, GREEN ON WHITE			E-136B E-136B
	VERMONT 15 VERMONT 117	1 1	24 30	24 24	4.00 5.00																										SIGN ID CODE MI-5, GREEN ON WHITE SIGN ID CODE MI-5, GREEN ON WHITE			E-136B E-136B
		1 1	21 21	15 15	2.19 2.19																										SIGN ID CODE M6-1L GREEN ON WHITE SIGN ID CODE M6-1, GREEN ON WHITE			E-136B E-136B
	EXPOSITION						1																								SIGNS TO BE MOUNTED TO EXISTING POST SALVAGED SIGN TO BE MOUNTED TO EXISTING POST	-	-	-
L 36+59.0, RT	Main St Lincoln St Lincoln St	1	36	12		3.00			~~2~~	2					11.25 11.50			X													DOUBLE SIDED SIGN, SIGN ID CODE D3-1 TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGN ON POST. COST ASSOCIATED WITH THIS BRACKET WILL BE CONSIDERED INCIDENTAL TO THE SIGN POST.		60	
		1 1	48 48	12 12		4.00 4.00																									BACK-TO-BACK SIGN ID CODE D3-1 SIGN ID CODE D3-1 SIGNS TO BE MOUNTED TO SALVAGED POSTS.		60 60	
												LF	LF	LF	LF	LF 22.75	LF		EA		LB	LB	LB	LB								
		TOTALS			SF 67.52	SF 11.00	EA. 1	SF				LF			LF 22.75					EA.	LB				EA.	EA.	LB						

NOTES: 1. FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

2. SIGN AREAS LABELED IN THIS COLUMN WILL BE PAID FOR UNDER ITEM 900.670 SPECIAL PROVISION (TRAFFIC SIGNS, EXTRUDED).

CHA

PROJECT NAME: ESSEX JUNCTION
PROJECT NUMBER: STP 2956(I)

FILE NAME: zl4v25itss.dgn
PROJECT LEADER: D.GOZALKOWSKI
DESIGNED BY: J. OLSEN
TRAFFIC SIGN SUMMARY SHEET 9

PLOT DATE: 4/19/2016
DRAWN BY: A. KIRBY
CHECKED BY: J. SHIELDS
SHEET 49 OF 171