STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 12

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS																	REMARKS	SIGN DETAIL		
			WIDTH (in)	HEIGHT (in)	"A"	SEE NOTE 2	SALV SIGN	SALV TIS	RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft			SQUARE STEEL (in) lb/ft			ANCHOR	SLEEVE	TUBULAR STEEL Ø (in) lb/ft					W-SHAPE STEEL				SIGN FRAME REQUIRED	SHSM = FHWA STANDARD HIGHWAY SIGNS AND MARKINGS BOOK	DETAIL IN SHSM	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
															1.8	2.0	2.5			FOUND-ATION	3.0	3.5	4.0	5.0	FTG. SIZE		WEIGHT	POST SIZE				
												1.12	2.0	3.0	1.88	2.42	3.35				7.6	9.0	10.8	14.6	24"	30"						
ESSEX JUNCTION VT ROUTE 15 MN 121+20.0, LT	PARKING PARKING						I I				I						X 12.00	X												BACK - TO - BACK SALVAGED SIGNS TO BE MOUNTED ON NEW POST	- -	- -	- -
	DO NOT BLOCK INTERSECTION	I	24	30	5.00																									R10-7		
MN 121+64.0, LT	ONE WAY ONE WAY	I I	36 36	12 12	3.00 3.00						I					X 12.00		X												BACK - TO - BACK	R6-1R R6-1L		
MN 121+89.0, LT	Ivy Ln Main St 0150 0406 0230	I	36	12		3.00					I					X 11.00		X												DOUBLE SIDED SIGN, SIGN ID CODE D3-1 TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGNS ON POST. COSTS ASSOCIATED WITH THIS BRACKET WILL BE CONSIDERED INCIDENTAL TO THE SIGN POST		156	
		I	36	12		3.00																							DOUBLE SIDED SIGN, SIGN ID CODE D3-1		156	
		I	6	10	0.42																								SIGN ID CODE VD-700			T-44
MN 122+17.0, RT	EAST	I	24	12	2.00				~~1~~		1					14.00		X												SIGN ID CODE M3-2, GREEN ON WHITE			E-136B
	VERMONT 15	I	24	24	4.00																									SIGN ID CODE MI-5, GREEN ON WHITE SIGNS TO BE MOUNTED TO EXISTING POST			E-136B
MN 122+72.0, LT	JCT	I	21	15	2.19						I					X 14.25		X												SIGN ID CODE M2-1, GREEN ON WHITE			E-136B
	VERMONT 2A	I	24	24	4.00																									SIGN ID CODE MI-5, GREEN ON WHITE			E-136B
MN 123+39.0, LT	ONLY	I	36	30	7.50						I					X 13.25		X												SIGN ID CODE VR-922L			E-145A
											LF	LF	LF		LF	LF ~~56~~ 64.50	LF ~~14~~ 12.00	EA		LB	LB	LB	LB								
				TOTALS	SF 31.11	SF 6.00	EA. 2	SF			LF				LF	~~70~~ 76.50				EA.	LB				EA.	EA.	LB					

NOTES: 1. FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

2. SIGN AREAS LABELED IN THIS COLUMN WILL BE PAID FOR UNDER ITEM 900.670 SPECIAL PROVISION (TRAFFIC SIGNS, EXTRUDED).

CHA

PROJECT NAME: ESSEX JUNCTION
PROJECT NUMBER: NH 2956(2)

FILE NAME: z15v026tss.dgn
PROJECT LEADER: D.GOZALKOWSKI
DESIGNED BY: J. SCUDDER
TRAFFIC SIGN SUMMARY SHEET 12

PLOT DATE: 5/2/2016
DRAWN BY: C. KAHLBAUGH
CHECKED BY: J. SHIELDS
SHEET 130 OF 171