STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 24

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS																		REMARKS	SIGN DETAIL		
			WIDTH (In)	HEIGHT (In)	"A"	SEE NOTE 2	SALV SIGN	SALV TIS	RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft			SQUARE STEEL (In) lb/ft			ANCHOR	SLEEVE	FOUND-ATION	TUBULAR STEEL Ø (In) lb/ft				W-SHAPE STEEL FTG. SIZE		WEIGHT	POST SIZE	SIGNS REQUIRED FRAME	SHSM = FHWA STANDARD HIGHWAY SIGNS AND MARKINGS BOOK	DETAIL IN SHSM	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
												1.12	2.0	3.0	1.8	2.0	2.5				3.0	3.5	4.0	5.0	24"	30"							
															1.88	2.42	3.35				7.6	9.0	10.8	14.6									
ESSEX JUNCTION VT ROUTE 15 MN 166+24.0, LT		1	30	30	6.25						1					X 14.75		X												SIGN SHALL HAVE FLUORESCENT YELLOW GREEN BACKGROUND	WII-2		
		1	24	12	2.00																									SIGN SHALL HAVE FLUORESCENT YELLOW GREEN BACKGROUND	WI6-7P		
MN 166+41.0, LT	Athens Dr / Main St / STOP / 0150 0406 0316	1	30	9 ~~8~~		1.88 ~~1.66~~					1						X 13.50	X												DOUBLE SIDED SIGN, SIGN ID CODE D3-1 TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGNS ON POST. COSTS ASSOCIATED WITH THIS BRACKET WILL BE CONSIDERED INCIDENTAL TO THE SIGN POST		157	
		1	24	9 ~~8~~		1.50 ~~1.33~~																								DOUBLE SIDED SIGN, SIGN ID CODE D3-1		156	
		1 1	30 6	30 10	6.25 0.42																									BACK-TO-BACK SIGN ID CODE VD-700	RI-1		T-44
MN 166+82.0, LT	NO OUTLET	1	30	30	6.25						1					X 13.00		X													WI4-2		
MN 169+50.0, LT	SNOW REMOVAL TOW ZONE ALL STREETS DEC 1 - APR 1 12 AM - 7 AM AT OWNERS EXPENSE						1				1					X 13.25		X												SALVAGED SIGN TO BE MOUNTED ON NEW POST	-	-	-
MN 170+73.0, LT	SPEED LIMIT 30	1	30	36	7.50				~~2~~		1					14.25														NEW POST AND SIGN INSTALLED ~~SIGN TO BE MOUNTED ON EXISTING POSTS~~	R2-1		
MN 171+85.0, LT	STATE HIGHWAY ENDS	1	24	18	3.00						1					X 13.00		X												SIGN ID CODE VR-038			T-71
												LF	LF	LF	LF	~~56~~	~~14~~	EA			LB	LB	LB	LB									
																68.25	13.50															
		TOTALS	SF 31.67		SF ~~2.99~~ 3.38		EA. 1	SF				LF			LF ~~70~~ 81.75					EA.	LB				EA.	EA.	LB						

NOTES: 1. FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

2. SIGN AREAS LABELED IN THIS COLUMN WILL BE PAID FOR UNDER ITEM 900.670 SPECIAL PROVISION (TRAFFIC SIGNS, EXTRUDED).

CHA

PROJECT NAME: ESSEX JUNCTION
PROJECT NUMBER: NH 2956(2)

FILE NAME: z15v026tss.dgn
PROJECT LEADER: D.GOZALKOWSKI
DESIGNED BY: J. SCUDDER
TRAFFIC SIGN SUMMARY SHEET 24

PLOT DATE: 5/2/2016
DRAWN BY: C. KAHLBAUGH
CHECKED BY: J. SHIELDS
SHEET 142 OF 171