

TRAFFIC SIGN SUMMARY SHEET 25

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS		NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS														REMARKS SHSM = FHWA STANDARD HIGHWAY SIGNS AND MARKINGS BOOK	SIGN DETAIL								
		WIDTH (in)	HEIGHT (in)	"A"	SEE NOTE 2	SALV SIGN	SALV TIS	RETA IN	SALV AGE	NO. OF POSTS	FLANGED CHANNEL			SQUARE STEEL (in)			TUBULAR STEEL Ø (in)				W-SHAPE STEEL				DETAIL IN SHSM	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER						
											1.2	2.0	3.0	1.8	2.0	2.5	ANCHOR	SUPPORT	VE	FOUND-ATION	3.0	3.5	4.0					5.0	FTG. SIZE		WEIGHT	POST SIZE	
																													lb/ft	lb/ft			lb/ft
ESSEX JUNCTION VT ROUTE 15 MN 171+85.0, RT		24	18	3.00					I				X														SIGN ID CODE VR-039			T-71			
		24	30	5.00																									R2-1				
		6	10	0.42																										T-44			
ESSEX JUNCTION VT ROUTE 117 MA 7+39.0, RT		30	30	6.25					I				X																	SIGN SHALL HAVE FLUORESCENT YELLOW GREEN BACKGROUND	W11-2		
		24	12	2.00																										SIGN SHALL HAVE FLUORESCENT YELLOW GREEN BACKGROUND	W16-7P		
MA 7+90.0, RT		24	9	1.50					I				X																	DOUBLE SIDED SIGN, SIGN ID CODE D3-1 TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGNS ON POST. COSTS ASSOCIATED WITH THIS BRACKET WILL BE CONSIDERED INCIDENTAL TO THE SIGN POST	157		
		30	9	1.88																											DOUBLE SIDED SIGN, SIGN ID CODE D3-1	157	
		30	30	6.25																											BACK-TO-BACK SIGN ID CODE VD-700	RI-1	T-44
		6	10	0.42																													
MA 7+93.0, LT		30	30	6.25					I				X																		SIGN SHALL HAVE FLUORESCENT YELLOW GREEN BACKGROUND	W11-2	
		24	12	2.00																											SIGN SHALL HAVE FLUORESCENT YELLOW GREEN BACKGROUND	W16-7P	
MA 8+39.0, LT		24	30	5.00					I				X																			R2-1	
MA 9+12.0, RT		24	30	5.00					I				X																			R2-1	
NOTES: 1. FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."												LF	LF	LF	LF	LF	LF	EA	LB	LB	LB	LB											
2. SIGN AREAS LABELED IN THIS COLUMN WILL BE PAID FOR UNDER ITEM 900.670 STANDARD PROVISION (TRAFFIC SIGNS, EXTRUDED).												LF	LF	LF	LF	LF	EA	LB	EA.	EA.	LB												
		TOTALS		SF	SF	EA.	SF				LF	LF	LF	EA.	LB	EA.	EA.	LB															
				41.59	2.99																												
					3.38																												

PROJECT NAME: ESSEX JUNCTION
PROJECT NUMBER: NH 2956(2)

FILE NAME: z15v026fss.dgn
PROJECT LEADER: D.GOZALKOWSKI
DESIGNED BY: J. SCUDDER
TRAFFIC SIGN SUMMARY SHEET 25

PLOT DATE: 5/2/2016
DRAWN BY: C. KAHLBAUGH
CHECKED BY: J. SHIELDS
SHEET 143 OF 171