

Signal Visors

Aluminum
Polycarbonate

45° Angle
Cap
Full Circle
Scoop
Tunnel



Cabinets
Controllers
Signals
Signs
Software
Specialty

Overview

McCain's Signal Visors increase signal visibility in sunlight while still allowing an unobstructed view for multiple lanes of approaching drivers and pedestrians. McCain produces a range of standard and angled visors including tunnel, full circle, and cap, that offer a variety of signal viewing angles. Whether you are looking for aluminum or polycarbonate, Federal yellow, signal green, black, or custom colors, McCain has the visors to meet your needs.

Benefits

- Increases signal visibility in sunlight
- Available in a variety of materials, sizes, styles, and angles to meet your specific requirements
- Twist-on tabs facilitate ease of installation
- One-piece construction (except Scoop Visor)

Product Description

McCain's Signal Visors, molded polycarbonate or stamped and formed aluminum, are available in eight inch and 12 inch signal configurations. Integrally formed, twist-on mounting tabs make installation and maintenance a snap, and a standard three degree downward tilt facilitates signal visibility.

Specialty visors include the 45° Angle Visor and the Scoop Visor. The 45° Angle Visor comes in two standard lengths, 18" and 27" and in right and left versions. It is designed to narrow visibility for locations such as an angled intersection.

The Scoop Visor is designed to resist snow build-up on signal lenses in colder climates. A louvered vent on top and an open bottom contribute to the increased vertical movement of air across the face of the signal lens thereby increasing resistance to the deposit of snow.