

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
								BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								1		1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
								720		720		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10				
								8		8		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35				
								1		1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50				
								5		5		CY	CONCRETE, HIGH PERFORMANCE CLASS A	501.33				
								400		400		LB	REINFORCING STEEL, LEVEL I	507.11				
								21		21		GAL	WATER REPELLENT, SILANE	514.10				
								82		82		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10				
								290		290		SY	SHEET MEMBRANE WATERPROOFING, TORCH APPLIED	519.20				
								82		82		LF	JOINT SEALER, HOT POURED	524.11				
								72		72		LF	REMOVAL OF EXISTING BRIDGE RAILING	525.10				
								72		72		LF	RESET EXISTING BRIDGE RAILING	525.11				
								290		290		SY	REMOVAL OF BRIDGE PAVEMENT	529.10				
								11		11		CY	REMOVAL OF CONCRETE OR MASONRY	529.25				
								100		100		SY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS I	580.10				
								50		50		SY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS II	580.11				
								10		10		CY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS III	580.12				
								2600		2600		SF	SURFACE PREPARATION FOR MEMBRANE	580.16				
								5		5		CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20				
								10		10		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25				
								10		10		HR	TRUCK RENTAL	608.37				
								50		50		HR	TRUCK-MOUNTED ATTENUATOR	608.45				
								10		10		LF	VERTICAL GRANITE CURB	616.21				
								30		30		GAL	REPOINTING GRANITE BRIDGE CURB	616.225				
								10		10		LF	GRANITE BRIDGE CURB	616.22				
								165		165		LF	REMOVING AND RESETTING CURB	616.40				
								45		45		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 6 INCH	618.10				
								420		420		LF	TEMPORARY TRAFFIC BARRIER	621.90				
								190		190		LF	REMOVE AND RESET TEMPORARY TRAFFIC BARRIER	621.95				
								50		50		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
								200		200		HR	FLAGGERS	630.15				
									1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
									1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
								1		1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
								1		1		LS	TRAFFIC CONTROL	641.10				
								3		3		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
								500		500		LF	4 INCH WHITE LINE	646.20				
								500		500		LF	4 INCH YELLOW LINE	646.21				
								1500		1500		LF	TEMPORARY 4 INCH WHITE LINE, TEMPORARY PAVEMENT MARKING TAPE	646.6011				
								500		500		LF	TEMPORARY 4 IN YELLOW LINE, TEMPORARY PAVEMENT MARKING TAPE	646.6111				

PROJECT NAME: DANVILLE
PROJECT NUMBER: BF MEMB(36)

FILE NAME: z13e114frm.dgn
PROJECT LEADER: G. BOGUE
DESIGNED BY: D. DEBAIE
QUANTITY SHEET QS-01

PLOT DATE: 6/12/2014
DRAWN BY: D. GROVER
CHECKED BY: D. DEBAIE
SHEET 4 OF 22

