DIRECTION	MILEPOINT	LOCATION CODE (SHEET 3)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
EB NEW HAVEN VT 17							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
		A	S1-1	36	36	FYG	(CONT.)	9.00								2		13.75 13.50 X								INSTALL BEHIND SIDEWALK. PROVIDE 7' MIN. VERTICAL CLEARANCE.	X		
		A	W16-7P	24	12	FYG		2.00																				X		
EB	4.867	AB	D-3	4	13		SOUTH STREET						1		X												SOUTH ST (TH-6)			
		AB	D3-1	39	12			3.25								1		10.75 X								INSTALL INDEPENDENTLY ON LEGAL LOAD SIDE OF INTERSECTION. INSTALL BEHIND SIDEWALK. PROVIDE 7' MIN. VERTICAL CLEARANCE.		12	
EB	4.867	C	VR-017	24	24		LLL 24,000 LBS						1		X															
		C	R2-1	18	24		SPEED LIMIT 35				1		1																	
		D	R1-1	24	24		STOP						1																	
		C	VR-017	24	30			5.00								1		15.00 X											E-141
		C	R2-1	18	24		SPEED LIMIT 35					1														INSTALL SPEED LIMIT SIGN BELOW NEW LLL24K SIGN			
EB	4.875	D	R1-1	30	30		STOP						1		X															
		D	R1-1	30	30			6.25								1		13.00 X								INSTALL BEHIND SIDEWALK RAMP IN ISLAND. PROVIDE 7' MIN. VERTICAL CLEARANCE	X		
		C	VD-700	6	10		0170 0113 0487	0.42																		INSTALL BACK TO BACK ON STOP SIGN POST			T-44
EB	4.890	A	R2-1	24	30								1		X															
		A	R2-1	24	30			5.00								1		13.00 X										X		
SIGN SUMMARY SHEET							SHEET TOTALS	30.92	0.00	0	1	1	6	0	0	6		~~90.0~~ 79.00		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	218.4	0.0	3	3	3	49	0	0	40		590.0		0	0.0								

PROJECT NAME: **STATEWIDE-SOUTHWEST**
PROJECT NUMBER: **STPG SIGN(51)**
FILE NAME: **z13e624tssnewhaven EB**
PROJECT MANAGER: **C. BEAN**
DESIGNED BY: **S. GOODWIN**
NEW HAVEN VT-17 EASTBOUND 4
PLOT DATE: **4/28/2015**
DRAWN BY: **S. GOODWIN**
CHECKED **D. MUNRO**
SHEET **16** OF **121**