DIRECTION	MILEPOINT	LOCATION CODE (SHEET 3)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
EB NEW HAVEN VT 17							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
EB	5.304	A	W1-4L	30	30			6.25								1		13.75 X								INSTALL 150 FT ± EAST OF EXISTING SIGN AT MP 5.276	X		
		A	W13-1P	18	18		35 MPH	2.25																			X		
EB	5.358	A	W1-6	48	24								1		X														
		A	W1-6	48	24			8.00								2		11.75 12.25 X									X		
EB	5.472	A	W1-2R	30	30		RIGHT CURVE						1		X														
		A	W13-1P	18	18		35 M.P.H (PLAQUE)						1																
EB	5.490	A	S3-1	30	30		SCHOOL BUS STOP AHEAD						1		X														
		A	S3-1	36	36	FYG		9.00								2		13.00 13.00 X									X		
EB	6.363	AB	D-3	18	6		EAST ST						1		X											EAST ST (TH-22)			
		CD	D-3	24	6		MAIN ST RT17						1													RETURN TO TOWN			
EB	6.370	C	VR-017	24	30		LLL 24,000 LBS				1		1		X														
		C	VR-700	6	8		MILE MARKER 0170 / 0113 / 0634						1																
		D	R1-1	30	30		STOP						1																
		D	R1-1	30	30			6.25								1		13.00 X									X		
		C	VD-700	6	10		0170 0113 0634	0.42																		INSTALL BACK TO BACK ON STOP SIGN POST			T-44
							SHEET TOTALS	32.17	0.00	0	1	0	9	0	0	6		~~90.0~~ 76.75		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	218.4	0.0	3	3	3	49	0	0	40		590.0		0		0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: STATEWIDE-SOUTHWEST
PROJECT NUMBER: STPG SIGN(51)

FILE NAME: z13e624tssnewhaven EB
PROJECT MANAGER: C. BEAN
DESIGNED BY: S. GOODWIN
NEW HAVEN VT-17 EASTBOUND 6

PLOT DATE: 4/28/2015
DRAWN BY: S. GOODWIN
CHECKED D. MUNRO