DIRECTION	MILEPOINT	LOCATION CODE (SHEET 3)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
EB NEW HAVEN VT 17							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
EB	6.370	AB	D3-1	33	12		East St	2.75								1		10.75 X								INSTALL INDEPENDENTLY ON STOP SIGN SIDE OF INTERSECTION		12	
EB	6.370	C	VR-017	24	30		LLL 24,000 LBS					1				1		13.00 X								INSTALL ON LEGAL LOAD SIDE OF EAST ST			
EB	6.436	AB	D-3	18	6		EAST ST						1		X														
		CD	D-3	24	6		MAIN ST RT17						1													RETURN TO TOWN			
EB	6.436	C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								1		13.00 X								INSTALL ON LEGAL LOAD SIDE OF TOWN HIGHWAY			E-141
EB	6.439	AB	D3-1	33	12		East St	2.75								1		11.50 X								INSTALL INDEPENDENTLY ON LEGAL LOAD SIDE OF INTERSECTION		12	
EB	6.448	C	VR-017	24	24		LLL 24,000 LBS						1		X														
		D	R1-1	30	30		STOP						1																
		A	VR-700	6	8		MILE MARKER 0170 / 0113 / 0646						1																	
		D	R1-1	30	30		STOP 0170 0113 0646	6.25								1		13.75 X									X		
		C	VD-700	6	10			0.42																		INSTALL BACK TO BACK ON STOP SIGN POST			T-42
EB	6.590	A	M3-2	24	12		EAST VERMONT 17	2.00								1		14.75 X								EAST, **GREEN ON WHITE**			E-136B
		A	VM1-5	24	24			4.00																					E-136B
EB	6.643	A	R2-1	24	30		SPEED LIMIT 45			1				X															
							SHEET TOTALS	23.17	0.00	1	0	1	5	0	0	6		~~90.0~~ 76.75		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	218.4	0.0	3	3	3	49	0	0	40		590.0		0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE-SOUTHWEST**
PROJECT NUMBER: **STPG SIGN(51)**

FILE NAME: **z13e624tssnewhaven EB**
PROJECT MANAGER: **C. BEAN**
DESIGNED BY: **S. GOODWIN**
NEW HAVEN VT-17 EASTBOUND 7

PLOT DATE: **4/28/2015**
DRAWN BY: **S. GOODWIN**
CHECKED **D. MUNRO**
SHEET **19** OF **121**