DIRECTION	MILEPOINT	LOCATION CODE (SHEET 3)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
EB BRISTOL VT 17							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
		A	W7-3aP	24	18		NEXT 2 MILES (CONT.)						1																
		A	W1-5L	30	30			6.25																			X		
		A	W7-3aP	24	18		NEXT 2 MILES	3.00																			X		
EB	0.849	A	VD-701	6	8		BRIDGE 12 VT-17						1		X														
		A	VD-701	6	10			0.42								1	8.50 X												T-42
EB	0.860	A	W1-2R	30	30	FY		6.25								1		15.50 X								INSTALL 60 FT ± EAST OF BRIDGE MARKER AT MP 0.849	X		
		A	W13-1P	18	18	FY	40 MPH	2.25																			X		
EB	1.650	A	VD-701	6	10		BRIDGE 13 VT-17	0.42								1	6.50 X												T-42
EB	1.961	A	VW-285	36	36		FALLING ROCK SYMBOL						1		X														
		A	VD-701	6	8		BRIDGE 13A VT17						1																
		A	VW-285	30	30			6.25								1		13.50 X									7	
EB	1.964	A	VD-701	6	10		BRIDGE 13A VT-17	0.42								1	7.50 X												T-42
EB	2.265	A	VD-701	6	8		BRIDGE 14 VT-17						1		X														
		A	VD-701	6	10			0.42								1	8.00 X												T-42
							SHEET TOTALS	25.68 ~~25.67~~	0.00	0	0	0	5	0	0	6		~~70.0~~ 59.50		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	129.9	0.0	4	1	1	33	0	0	20		275.0		0		0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: STATEWIDE-SOUTHWEST
PROJECT NUMBER: STPG SIGN(51)

FILE NAME: z13e624tss bristol EB
PROJECT MANAGER: C. BEAN
DESIGNED BY: S. GOODWIN
BRISTOL VT-17 EASTBOUND 5

PLOT DATE: 4/28/2015
DRAWN BY: S. GOODWIN
CHECKED: D. MUNRO