DIRECTION	MILEPOINT	LOCATION CODE (SHEET 3)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
WB BRISTOL VT 17							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
WB	0.082	F	W1-4R	30	30			6.25								1		14.00 X								INSTALL 150 FT ± WEST OF EXISTING SIGN AT MP 0.110	X		
WB	0.008	F	R2-1	24	30		SPEED LIMIT 45						1		X														
WB	0.000	F	R2-1	24	30			5.00								1		12.75 X								INSTALL 40 FT ± WEST OF EXISTING SIGN AT MP 0.008	X		
1	1.000	1	1	1	1	1																							
1	1.000	1	1	1	1	1																							
1	1.000	1	1	1	1	1																							
1	1.000	1	1	1	1	1																							
1	1.000	1	1	1	1	1																							
1	1.000	1	1	1	1	1																							
							SHEET TOTALS	11.25	0.00	0	0	0	1	0	0	2		~~30.0~~ 26.75		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	156.8	0.0	4	0	0	32	0	0	22		310.0		0		0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE-SOUTHWEST**
PROJECT NUMBER: **STPG SIGN(51)**

FILE NAME: **z13e624tssbristol WB**
PROJECT MANAGER: **C. BEAN**
DESIGNED BY: **S. GOODWIN**
BRISTOL VT-17 WESTBOUND 6

PLOT DATE: **4/28/2015**
DRAWN BY: **S. GOODWIN**
CHECKED BY: **D. MUNRO**