DIRECTION	MILEPOINT	LOCATION CODE (SHEET 3)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) (LB / FT) 1.75 / 1.88	SQUARE STEEL (IN) (LB / FT) 2.00 / 2.42	SQUARE STEEL (IN) (LB / FT) 2.50 / 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) (LB / FT) 3.00 / 7.60	TUBULAR STEEL Ø (IN) (LB / FT) 3.50 / 9.00	TUBULAR STEEL Ø (IN) (LB / FT) 4.00 / 10.80	TUBULAR STEEL Ø (IN) (LB / FT) 5.00 / 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
WB STARKSBORO VT 17							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
		EF	D3-1	36	12		Gore Rd 0170 0119 0521 (CONT.)	3.00								~~1~~		~~X~~								GORE RD (TH-4) MOUNT GORE RD PERP. ON TOP OF RETAINED STOP SIGN		12	
		G	VD-700	6	10			0.42																		INSTALL BACK TO BACK ON RETAINED STOP SIGN POST			T-44
WB	5.175	F	VD-701	6	10		BRIDGE 25 VT-17	0.42								1	8.25 X												T-42
WB	5.172	F	M3-4	24	12		WEST			1				X															
		F	M1-5	24	24		VERMONT 17			1																			
		F	VD-701	6	8		BRIDGE 25 VT 17						1																
WB	5.075	F	R2-1	24	30		SPEED LIMIT 50				1		1		X														
		F	R2-1	24	30		SPEED LIMIT 50					1				1		13.25 X											
WB	5.004	F	VD-701	6	10		BRIDGE 24 VT-17	0.42					1			1	9.00 X												T-42
WB	4.636	F	VD-701	6	8		BRIDGE 23 VT-17						1		X														
		F	VD-701	6	10			0.42								1	8.50 X												T-42
WB	4.529	F	VW-054L	30	30		HIDDEN DRIVE LEFT						1		X														
		F	VW-054L	30	30			6.25								1		14.25 X											E-154
WB	2.679	F	VD-701	6	8		BRIDGE 22 VT-17						1		X														
		F	VD-701	6	10			0.42								1	8.00 X												T-42
SIGN SUMMARY SHEET							SHEET TOTALS	11.35	0.00	2	1	1	~~5~~ 6	0	0	~~7~~ 6		~~85.0~~ 61.25		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	169.8	0.0	5	2	2	38	0	0	36		495.0		0	0.0								

PROJECT NAME: **STATEWIDE-SOUTHWEST**
PROJECT NUMBER: **STPG SIGN(51)**
FILE NAME: **z13e624tssstarksboro WB** PLOT DATE: **4/28/2015**
PROJECT MANAGER: **C. BEAN** DRAWN BY: **S. GOODWIN**
DESIGNED BY: **S. GOODWIN** CHECKED **D. MUNRO**
STARKSBORO VT-17 WESTBOUND 2 SHEET **49** OF **121**