DIRECTION	MILEPOINT	LOCATION CODE (SHEET 3)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
WB STARKSBORO VT 17							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
WB	1.156	G	VR-017	24	30								1	X															
		G	VR-017	24	30			5.00																			INSTALL NEW SIGN AT SAME LOCATION ON LAFAYETTE RD			E-141
WB	1.148	GH	D-3	12	4		ROUTE 17						1		X												RETURN TO TOWN			
		EF	D-3	18	4		LAFAYETTE RD						1																	
		H	R1-1	30	30		STOP						1																	
		G	VD-700	6	8		MILE MARKER 0170 / 0119 / 0115						1														LAFAYETTE RD (TH-31)			
		H	R1-1	30	30			6.25								1		12.50 X									X		
		G	VD-700	6	10			0.42																		INSTALL BACK TO BACK ON STOP SIGN POST			T-44
WB	1.148	EF	D3-1	51	12			4.25								2		9.75 10.00 X									INSTALL INDEPENDENTLY ON TWO POSTS ON THE STOP SIGN SIDE OF THE INTERSECTION		12	
WB	1.137	F	W1-4R	30	30			6.25								1		14.50 X									INSTALL 60 FT ± WEST OF STOP SIGN AT MP 1.148	X		
WB	0.947	F	VD-701	6	8								1		X															
		F	VD-701	6	10			0.42								1	7.25 X												T-42
WB	0.592	F	VD-062A	72	16		OFFICIAL BUSINESS DIRECTIONAL SIGN			1				X													Maple Hill C.G. quaker street			
							SHEET TOTALS	22.59 SF	0.00 SF	1 EA	0 EA	0 EA	6 EA	0 EA	0 EA	5 EA		~~70.0~~ 54.00 FT		0 EA	0.0 LB	0.0 LB	0.0 LB	0.0 LB				
							TOWN DIRECTIONAL TOTALS	169.8	0.0	5	2	2	38	0	0	36		495.0		0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE-SOUTHWEST**
PROJECT NUMBER: **STPG SIGN(51)**
FILE NAME: **z13e624tssstarksboro WB**
PROJECT MANAGER: **C. BEAN**
DESIGNED BY: **S. GOODWIN**
DRAWN BY: **S. GOODWIN**
CHECKED **D. MUNRO**
PLOT DATE: **4/28/2015**
STARKSBORO VT-17 WESTBOUND 5
SHEET **52** OF **121**