DIRECTION	MILEPOINT	LOCATION CODE (SHEET 3)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
WB FAYSTON VT 17							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
WB	4.208	G	M3-4	24	12		WEST			1				X														
		G	VM1-5	24	24		VERMONT 17			1																		
		G	M6-1	21	15		<--- LEFT			1																		
		G	M3-2	24	12		EAST			1																		
		G	VM1-5	24	24		VERMONT 17			1																		
		G	M6-1	21	15		RIGHT --->			1																		
		G	M4-5	21	12		TO			1																		
		G	VM1-5	30	24		VERMONT 100			1																		
		G	M6-1	21	15		RIGHT --->			1																		
WB	4.180	F	M3-4	24	12			2.00								1		14.00 X									WEST, GREEN ON WHITE INSTALL 150 FT ± WEST OF SIGN ASSEMBLY AT MP 4.208			E-136B
		F	VM1-5	24	24			4.00																					E-136B
WB	4.163	F	R2-1	24	30		SPEED LIMIT 40						1		X														
WB	4.145	F	R2-1	24	30			5.00								1		14.00 X									INSTALL 200 FT ± WEST OF NEW SIGN AT MP 4.180	X		
WB	3.937	F	W1-4R	30	30			6.25								1		15.00 X									INSTALL 150 FT ± EAST OF EXISTING SIGN AT MP 3.909	X		
							SHEET TOTALS	17.25	0.00	9	0	0	1	0	0	3		~~45.0~~ 43.00		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	386.6	0.0	19	0	0	60	0	0	57		835.0		0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE-SOUTHWEST**
PROJECT NUMBER: **STPG SIGN(51)**
FILE NAME: **z13e624tss favston WB**
PROJECT MANAGER: **C. BEAN**
DESIGNED BY: **S. GOODWIN**
FAYSTON VT-17 WESTBOUND 4
PLOT DATE: **4/28/2015**
DRAWN BY: **S. GOODWIN**
CHECKED **D. MUNRO**
SHEET **85** OF **121**