DIRECTION	MILEPOINT	LOCATION CODE (SHEET 3)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) (LB / FT) 1.75 / 1.88	SQUARE STEEL (IN) (LB / FT) 2.00 / 2.42	SQUARE STEEL (IN) (LB / FT) 2.50 / 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) (LB / FT) 3.00 / 7.60	TUBULAR STEEL Ø (IN) (LB / FT) 3.50 / 9.00	TUBULAR STEEL Ø (IN) (LB / FT) 4.00 / 10.80	TUBULAR STEEL Ø (IN) (LB / FT) 5.00 / 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
WB FAYSTON VT 17							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
WB	3.909	F	VW-054R	30	30		HIDDEN DRIVE RIGHT						1		X													
WB	3.900	F	VW-054R	30	30			6.25								1		14.75 X								INSTALL 50 FT ± WEST OF EXISTING SIGN AT MP 3.909			E-154
WB	3.380	F	W1-10d	36	36			9.00								2		15.00 15.00 X								INSTALL 275 FT ± EAST OF EXISTING SIGN AT MP 3.329	X		
		F	W16-8P	36	8			2.00																				7	
WB	3.329	F	S3-1	30	30		SCHOOL BUS STOP AHEAD						1		X													
		F	S3-1	36	36	FYG		9.00								2		14.25 14.50 X									X		
WB	3.276	F	VW1-2M	30	30		MODIFIED RIGHT CURVE						1		X													
WB	3.209	F	R2-1	24	30		SPEED LIMIT 40						1		X													
WB	3.179	EF		24	6		OLD MANSFIELD RD						1		X	2		11.25 10.50	THESE POSTS ARE ON THE SECOND SIGN PLACEMENT							OLD MANSFIELD RD (TH-29) RETURN WOOD POST AND STREET SIGNS TO TOWN			
		EF	D3-1	66	12		REPLACED SIGN WAS STOLEN &RE-INSTALLED	5.50 5.50								2		10.25 9.75 X								INSTALL INDEPENDENTLY ON TWO POSTS ON THE LEGAL LOAD SIDE OF THE INTERSECTION		12	
WB	3.176	G	VR-017	24	30								1		X													OLD MANSFIELD RD (TH-29)			
		G	VR-017	24	30			5.00								1		13.25 X								INSTALL NEW SIGN IN SAME LOCATION ON OLD MANSFIELD RD			E-141
WB	3.168	H	R1-1	30	30								1	X														
		G	VD-700	6	8		MILE MARKER 0170 / 1208 / 0319						1															
		H	R1-1	30	30		(CONT. ON NEXT SHEET)	6.25																				X	
SIGN SUMMARY SHEET							SHEET TOTALS	~~48.50~~ ~~43.00~~	0.00	0	0	0	8	0	0	~~8~~ 10		~~120.0~~ 128.50		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	386.6	0.0	19	0	0	60	0	0	57		835.0		0	0.0								

PROJECT NAME: **STATEWIDE-SOUTHWEST**
PROJECT NUMBER: **STPG SIGN(51)**
FILE NAME: **z13e624tss favston WB**
PROJECT MANAGER: **C. BEAN**
DESIGNED BY: **S. GOODWIN**
FAYSTON VT-17 WESTBOUND 5
PLOT DATE: **4/28/2015**
DRAWN BY: **S. GOODWIN**
CHECKED **D. MUNRO**
SHEET **86** OF **121**