| DIRECTION | MILEPOINT | LOCATION CODE (SHEET 3) | SIGN CODE | WIDTH (IN) | HEIGHT (IN) | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXIST POST RETAIN | EXIST POST REMOVE | NUMBER OF NEW POSTS | SQUARE STEEL (IN) (LB / FT) 1.75 / 1.88 | SQUARE STEEL (IN) (LB / FT) 2.00 / 2.42 | SQUARE STEEL (IN) (LB / FT) 2.50 / 3.35 | TUBULAR STEEL Ø (IN) FOUNDATION | TUBULAR STEEL Ø (IN) (LB / FT) 3.00 / 7.60 | TUBULAR STEEL Ø (IN) (LB / FT) 3.50 / 9.00 | TUBULAR STEEL Ø (IN) (LB / FT) 4.00 / 10.80 | TUBULAR STEEL Ø (IN) (LB / FT) 5.00 / 14.60 | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL LOCATION SHSM | SIGN DETAIL LOCATION PROJECT SHEET # | SIGN DETAIL LOCATION STANDARD SHEET # |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **WB FAYSTON VT 17** | | | | | | | FY-FLUORESCENT YELLOW<br>FYG-FLUORESCENT YELLOW GREEN | | | | | | | | | | | | | | | | | | | "SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK | | | |
| | | G | VD-700 | 6 | 10 | | 0170 1208 0319 (CONT.) | 0.42 | | | | | | | | | | | | | | | | | | INSTALL BACK TO BACK ON STOP SIGN POST | | | T-44 |
| WB | 3.087 | F | VD-701 | 6 | 8 | | BRIDGE 34 VT-17 | | | | | | 1 | | X | | | | | | | | | | | | | |
| | | F | VD-701 | 6 | 10 | | | 0.42 | | | | | | | | 1 | 7.00 X | | | | | | | | | | | T-42 |
| WB | 3.067 | F | OM3-R | 12 | 36 | | RIGHT OBJECT MARKER | | | | | | 1 | | X | | | | | | | | | | | | | |
| WB | 3.057 | E | OM3-L | 12 | 36 | | LEFT OBJECT MARKER | | | | | | 1 | | X | | | | | | | | | | | | | |
| WB | 3.043 | F | VW-054L | 30 | 30 | | HIDDEN DRIVE LEFT | | | | | | 1 | X | | | | | | | | | | | | | | |
| | | F | R2-1 | 24 | 30 | | SPEED LIMIT 40 | 5.00 | | | | | | | | | | | | | | | | | | | X | |
| WB | 2.996 | F | VW-054L | 30 | 30 | | HIDDEN DRIVE LEFT | 6.25 | | | | | | | | 1 | 15.00 X | | | | | | | | | INSTALL 250 FT± WEST OF EXISTING SIGN AT MP 3.043 | | | E-154 |
| WB | 2.425 | F | W1-5L | 30 | 30 | FY | NEXT 2 MILES | 6.25 | | | | | | | | 1 | 16.75 X | | | | | | | | | INSTALL 750 FT± WEST OF EXISTING EB SL 40 AT MP 2.567 | X | | |
| | | F | W7-3aP | 24 | 18 | FY | | 3.00 | | | | | | | | | | | | | | | | | | | X | |
| WB | 2.367 | F | W1-1L | 30 | 30 | FY | | 6.25 | | | | | | | | 1 | 15.75 X | | | | | | | | | INSTALL 300 FT ± WEST OF NEW SIGN AT MP 2.425 | X | | |
| | | F | W13-1P | 18 | 18 | FY | 30 MPH | 2.25 | | | | | | | | | | | | | | | | | | | X | |
| WB | 2.315 | F | W1-8 | 18 | 24 | | LEFT CHEVRON | | | | | | 1 | | X | | | | | | | | | | | | | |
| WB | 2.315 | E | W1-8 | 18 | 24 | | RIGHT CHEVRON | | | | | | 1 | | X | | | | | | | | | | | | | |
| WB | 2.308 | F | W1-8 | 18 | 24 | FY | | 3.00 | | | | | | | | 1 | 11.25 X | | | | | | | | | INSTALL 35 FT ± WEST OF EXISTING CHEVRONS AT MP 2.315 | X | | |
| | | | | | | | SHEET TOTALS | 32.84 | 0.00 | 0 | 0 | 0 | 6 | 0 | 0 | 5 | ~~70.0~~ 65.75 | | | 0 | 0.0 | 0.0 | 0.0 | 0.0 | | | | |
| | | | | | | | | SF | SF | EA | EA | EA | EA | EA | EA | EA | FT | | | EA | LB | LB | LB | LB | | | | |
| | | | | | | | TOWN DIRECTIONAL TOTALS | 386.6 | 0.0 | 19 | 0 | 0 | 60 | 0 | 0 | 57 | 835.0 | | | 0 | 0.0 | | | | | | | |

# SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE-SOUTHWEST**
PROJECT NUMBER: **STPG SIGN(51)**

FILE NAME: **z13e624tss favston WB** PLOT DATE: **4/28/2015**
PROJECT MANAGER: **C. BEAN** DRAWN BY: **S. GOODWIN**
DESIGNED BY: **S. GOODWIN** CHECKED **D. MUNRO**
FAYSTON VT-17 WESTBOUND 6 SHEET **87** OF **121**