| DIRECTION | MILEPOINT | LOCATION CODE (SHEET 3) | SIGN CODE | WIDTH (IN) | HEIGHT (IN) | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXIST POST RETAIN | EXIST POST REMOVE | NUMBER OF NEW POSTS | SQUARE STEEL (IN) (LB / FT) 1.75 / 1.88 | SQUARE STEEL (IN) (LB / FT) 2.00 / 2.42 | SQUARE STEEL (IN) (LB / FT) 2.50 / 3.35 | TUBULAR STEEL Ø (IN) FOUNDATION | TUBULAR STEEL Ø (IN) (LB / FT) 3.00 / 7.60 | TUBULAR STEEL Ø (IN) (LB / FT) 3.50 / 9.00 | TUBULAR STEEL Ø (IN) (LB / FT) 4.00 / 10.80 | TUBULAR STEEL Ø (IN) (LB / FT) 5.00 / 14.60 | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL LOCATION SHSM | SIGN DETAIL LOCATION PROJECT SHEET # | SIGN DETAIL LOCATION STANDARD SHEET # |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **WB FAYSTON VT 17** | | | | | | | FY-FLUORESCENT YELLOW<br>FYG-FLUORESCENT YELLOW GREEN | | | | | | | | | | | | | | | | | | | "SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK | | | |
| | | E | W1-8 | 18 | 24 | FY | (CONT.) | 3.00 | | | | | | | | | | | | | | | | | | X | | |
| WB | 1.730 | F | OM3-R | 12 | 36 | | RIGHT OBJECT MARKER | | | | | | 1 | | X | | | | | | | | | | | | | | |
| WB | 1.718 | E | OM3-L | 12 | 36 | | LEFT OBJECT MARKER | | | | | | 1 | | X | | | | | | | | | | | | | | |
| WB | 1.718 | F | W1-8 | 18 | 24 | | | | | | | | 1 | X | | | | | | | | | | | | | | | |
| | | F | W1-8 | 18 | 24 | FY | | 3.00 | | | | | | | | | | | | | | | | | | X | | |
| WB | 1.718 | E | W1-8 | 18 | 24 | | | | | | | | 1 | X | | | | | | | | | | | | | | | |
| | | E | W1-8 | 18 | 24 | FY | | 3.00 | | | | | | | | | | | | | | | | | | X | | |
| WB | 1.418 | F | W11-2 | 30 | 30 | FYG | | 6.25 | | | | | | | | 1 | | 15.75 X | | | | | | | | INSTALL 200 FT ± EAST OF PROPOSED SIGN AT WB MP 1.380 | X | | |
| | | F | W16-4P | 30 | 24 | FYG |  | 5.00 | | | | | | | | | | | | | | | | | | X | | |
| WB | 1.380 | F | W1-11R | 30 | 30 | FY | | 6.25 | | | | | | | | 1 | | 14.75 X | | | | | | | | INSTALL 150 FT ± EAST OF EXISTING SIGN AT MP 1.352 | X | | |
| | | F | W13-1P | 24 | 24 | FY |  | 4.00 | | | | | | | | | | | | | | | | | | X | | |
| WB | 1.352 | F | W11-2 | 30 | 30 | | PEDESTRIAN | | | | | | 1 | | X | | | | | | | | | | | | | | |
| | | E | VR-020 | 24 | 30 | | NO PARKING ON TRAVELED LANE | | | | | | 1 | | | | | | | | | | | | | INSTALLED ON BACK | | | |
| | | F | VR-020 | 24 | 30 | | | 5.00 | | | | | | | | 1 | | 13.25 X | | | | | | | | | | E-146 |
| | | E | VR-020 | 24 | 30 | | | 5.00 | | | | | | | | | | | | | | | | | INSTALL BACK TO BACK | | | E-146 |
| | | | | | | | SHEET TOTALS | 40.50 SF | 0.00 SF | 0 EA | 0 EA | 0 EA | 6 EA | 0 EA | 0 EA | 3 EA | | ~~45.0~~ 43.75 FT | | 0 EA | 0.0 LB | 0.0 LB | 0.0 LB | 0.0 LB | | | | |
| | | | | | | | TOWN DIRECTIONAL TOTALS | 386.6 | 0.0 | 19 | 0 | 0 | 60 | 0 | 0 | 57 | | 835.0 | | 0 | 0.0 | | | | | | | |

# SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE-SOUTHWEST**
PROJECT NUMBER: **STPG SIGN(51)**

FILE NAME: **z13e624tss favston WB**
PROJECT MANAGER: **C. BEAN**
DESIGNED BY: **S. GOODWIN**
FAYSTON VT-17 WESTBOUND 9

PLOT DATE: **4/28/2015**
DRAWN BY: **S. GOODWIN**
CHECKED **D. MUNRO**
SHEET **90** OF **121**