DIRECTION	MILEPOINT	LOCATION CODE (SHEET 3)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
WB FAYSTON VT 17							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
WB	0.565	F	W1-6	48	24	FY		8.00								2		11.75 11.50 X								INSTALL 40 FT± EAST OF EXISTING ARROW BOARD AT MP 0.558	X		
WB	0.563	E	W1-6	48	24	FY		8.00								2		11.50 11.75 X								INSTALL 30 FT± EAST OF EXISTING ARROW BOARD AT MP 0.558	X		
WB	0.558	E	W1-6	48	24		LARGE ARROW RIGHT						1		X														
WB	0.547	F	W1-6	48	24	FY		8.00								2		11.50 11.25 X								INSTALL 10 FT ± EAST OF EXISTING ARROW BOARD AT MP 0.545	X		
WB	0.545	E	W1-6	48	24								1	X																
		E	W1-6	48	24	FY		8.00																				X		
WB	0.511	F	W1-11R	30	30	FY		6.25								1		15.75								INSTALL 180 FT ± WEST OF EXISTING ARROW BOARD AT MP 0.545			
		F	W13-1P	24	24	FY		4.00																						
WB	0.398	E	W1-6	48	24		LARGE ARROW RIGHT						1		X															
WB	0.395	E	W1-6	48	24	FY		8.00								2		14.25 12.50 X								INSTALL 15 FT± WEST OF EXISTING ARROW BOARD AT MP 0.398	X		
WB	0.395	F	W1-6	48	24	FY		8.00								2		14.00 12.75 X									X		
WB	0.330	E	W1-6	48	24		LARGE ARROW RIGHT						1		X															
WB	0.294	F	R2-1	24	30			5.00								1		14.50 X								INSTALL 190 FT ± WEST OF EXISTING ARROW BOARD AT MP 0.330	X		
WB	0.183	A	W1-6	30	30			6.25								1		16.75 X								INSTALL 450 FT ± EAST OF EXISTING EASTBOUND ARROW BOARD AT MP 0.098		7	
		A	W7-3aP	24	18			3.00																				X		
SIGN SUMMARY SHEET							SHEET TOTALS	~~72.50~~ ~~62.25~~ SF	0.00 SF	0 EA	0 EA	0 EA	~~4~~ EA	0 EA	0 EA	~~13~~ ~~12~~ EA	~~169.75~~ ~~180.0~~ FT			0 EA	0.0 LB	0.0 LB	0.0 LB	0.0 LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	386.6	0.0	19	0	0	60	0	0	57	835.0			0	0.0								

PROJECT NAME: **STATEWIDE-SOUTHWEST**
PROJECT NUMBER: **STPG SIGN(51)**

FILE NAME: **z13e624tss favston WB** PLOT DATE: **4/28/2015**
PROJECT MANAGER: **C. BEAN** DRAWN BY: **S. GOODWIN**
DESIGNED BY: **S. GOODWIN** CHECKED **D. MUNRO**
FAYSTON VT-17 WESTBOUND 11 SHEET **92** OF **121**