DIRECTION	MILEPOINT	LOCATION CODE (SHEET 3)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
WB RUTLAND TOWN BUS 4							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
WB	0.711	F	M3-4	24	12		WEST						1	~~X~~															
		F	M4-3	24	12		BUSINESS						1																
		F	M1-4	24	24		US 4						1																
		F	M6-3	21	15		^UP ARROW						1																
		F	M3-1	24	12		NORTH						1																
		F	VM1-5	24	24		VERMONT 3						1																
		F	M6-1	21	15		RIGHT --->						1																
		F	M3-4	24	12			2.00																		2A	WEST, BLACK ON WHITE	X		
		F	M4-3	24	12			2.00																			BUSINESS, BLACK ON WHITE	X		
		F	M1-4	24	24			4.00																			US ROUTE 4	X		
		F	M6-3	21	15			2.19								2		16.25 15.00									UP ARROW, BLACK ON WHITE	X		
		F	M3-1	24	12			2.00																			NORTH, GREEN ON WHITE			E-136B
		F	VM1-5	24	24			4.00																			VT ROUTE 3			E-136B
		F	M6-2	21	15			2.19																			RIGHT ARROW (45 DEG.), GREEN ON WHITE			E-136B
WB	0.676	F	OM1-1	18	18		OBJECT MARKER (CONT. ON NEXT SHEET)						1		X														
							SHEET TOTALS	18.38	0.00	0	0	0	8	0	0	~~0~~ 2		~~0.0~~ 31.25		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	174.4	0.0	7	11	11	53	0	0	30		435.0		0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE-SOUTHWEST**
PROJECT NUMBER: **STPG SIGN(51)**

FILE NAME: **z13e624tss rutlandtown WB** PLOT DATE: **4/28/2015**
PROJECT MANAGER: **C. BEAN** DRAWN BY: **S. GOODWIN**
DESIGNED BY: **S. GOODWIN** CHECKED **D. MUNRO**
RUTLAND TOWN BUS-4 WESTBOUND 4 SHEET **116** OF **121**