

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
						ROADWAY	ROADWAY (NO FEDERAL/STATE)	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
														BEGIN OPTION CC					
						60	90				150		LF	18" CSP .064 (2-2/3 X 1/2)	601.0015				
						60	90				150		LF	18" CAAP .060 (2-2/3 X 1/2)	601.0215				
						60	90				150		LF	18" PCCSP .079 (2-2/3 X 1/2)	601.0416				
						60	90				150		LF	18" RCP CLASS III	601.0815				
						60	90				150		LF	18" CPEP	601.0915				
						60	90				150		LF	18" CPPP (SL)	601.2815				
														END OPTION CC					
						2	1				3		EACH	PRECAST REINFORCED CONCRETE DROP INLET WITH CAST IRON GRATE	604.18				
								1			1		MGAL	DUST CONTROL WITH WATER	609.10				
						90					90		CY	STONE FILL, TYPE I	613.10				
									225		225		CY	STONE FILL, TYPE III	613.12				
						30					30		LF	CAST-IN-PLACE CONCRETE CURB, TYPE B	616.28				
						2					2		EACH	WOOD MARKER POSTS	619.15				
						1					1		EACH	REMOVING AND RESETTING PROPERTY MARKERS	619.20				
						95					95		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED	621.21				
						1					1		EACH	MANUFACTURED TERMINAL SECTION, TANGENT	621.51				
						1					1		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60				
						4					4		EACH	GUARDRAIL APPROACH SECTION TO CONCRETE BRIDGE RAILING, TL-2	621.746				
						150					150		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
						20					20		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
						500					500		HR	FLAGGERS	630.15				
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
						1					1		LS	MOBILIZATION/DEMobilIZATION	635.11				
						6					6		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
						925					925		LF	4 INCH WHITE LINE	646.20				
						900					900		LF	4 INCH YELLOW LINE	646.21				
						1250					1250		SY	GEOTEXTILE FOR ROADBED SEPARATOR	649.11				
						325			300		625		SY	GEOTEXTILE UNDER STONE FILL	649.31				
								175			175		SY	GEOTEXTILE FOR SILT FENCE	649.51				
								75			75		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
								20			20		LB	SEED	651.15				
								40			40		LB	FERTILIZER	651.18				
								1			1		TON	AGRICULTURAL LIMESTONE	651.20				
								1			1		TON	HAY MULCH	651.25				
								45			45		CY	TOPSOIL	651.35				
									120		120		SY	GRUBBING MATERIAL	651.40				

PROJECT NAME: STRAFFORD
PROJECT NUMBER: BF 0177(10)
FILE NAME: s13j088qs.dgn PLOT DATE: 29-SEP-2016
PROJECT LEADER: K. HIGGINS DRAWN BY: T. MATTHEWS
DESIGNED BY: J. GRIGAS CHECKED BY: J. GRIGAS
QUANTITY SHEET 2 SHEET 6 OF 52