

QUANTITY SHEET 3

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
					ROADWAY	ROADWAY (NO FEDERAL/STATE)	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							1			1		LS	EPSC PLAN	652.10				
							40			40		HR	MONITORING EPSC PLAN	652.20				
							1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
							225			225		SY	TEMPORARY EROSION MATTING	653.20				
							36			36		CY	VEHICLE TRACKING PAD	653.35				
							3			3		EACH	INLET PROTECTION DEVICE, TYPE I	653.40				
							650			650		LF	BARRIER FENCE	653.50				
							650			650		LF	PROJECT DEMARCATION FENCE	653.55				
					0.66					0.66		SF	TRAFFIC SIGNS, TYPE A	675.20				
					35					35		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
					1					1		EACH	REMOVING SIGNS	675.50				
					1					1		EACH	ERECTING SALVAGED SIGNS	675.60				
					2					2		EACH	DELINEATOR WITH STEEL POST	676.10				
								50		50		CY	SPECIAL PROVISION (HIGH PERFORMANCE CONCRETE, RAPID SET) (FPQ)	900.608				
					36000					36000		DL	SPECIAL PROVISION (INCENTIVE/DISINCENTIVE) (N.A.B.I.)	900.615				
					5					5		EACH	SPECIAL PROVISION (CPM SCHEDULE)	900.620				
								118		118		LF	SPECIAL PROVISION (BRIDGE RAILING, TEXAS)(FPQ)	900.640				
								174		174		LF	SPECIAL PROVISION (PREFABRICATED BRIDGE UNIT SUPERSTRUCTURE)(FPQ)	900.640				
					1					1		LS	SPECIAL PROVISION (TRAFFIC CONTROL, ALL-INCLUSIVE)	900.645				
					1					1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, TYPE IVB) (N.A.B.I.)	900.650				
					225					225		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, TYPE IVB)	900.680				

PROJECT NAME: STRAFFORD
 PROJECT NUMBER: BF 0177(10)
 FILE NAME: s13j088qs.dgn PLOT DATE: 29-SEP-2016
 PROJECT LEADER: K. HIGGINS DRAWN BY: T. MATTHEWS
 DESIGNED BY: J. GRIGAS CHECKED BY: J. GRIGAS
 QUANTITY SHEET 3 SHEET 7 OF 52