



WINOOSKI VERY FINE SANDY LOAM
 0-3% SLOPE
 TYPE C SOIL
 K VALUE = 0.37
 HIGH EROSION POTENTIAL

BUCKLAND LOAM
 3-8% SLOPE
 TYPE C/D SOIL
 K VALUE = 0.32
 MODERATE EROSION POTENTIAL

NOTES:

1. FOR CLARITY, AREAS TO BE SEEDED AND MULCHED ARE NOT SHOWN; HOWEVER, ALL DISTURBED AREAS SHALL BE SEEDED AND MULCHED AS APPLICABLE.
2. EXISTING CONTOURS ARE SHOWN. SEE CROSS SECTIONS FOR FINAL CONTOURS.
3. THESE PLANS SHOW A CONCEPTUAL EROSION CONTROL PLAN, THE CONTRACTOR MUST SUBMIT A TEMPORARY EROSION CONTROL PLAN FOR APPROVAL.
4. THE CONTRACTOR SHALL USE OTHER EROSION CONTROL MEASURES AS NECESSITATED BY THE SEQUENCE OF CONSTRUCTION OR AS DIRECTED BY THE RESIDENT ENGINEER AND ON-SITE COORDINATOR.

EPSC PLAN

SCALE 1" = 20' - 0"
 20 0 20

PROJECT NAME:	STRAFFORD	PLOT DATE:	31-AUG-2016
PROJECT NUMBER:	BF 0177(10)	DRAWN BY:	J. GRIGAS
FILE NAME:	si3j088bdr_ero.dgn	CHECKED BY:	T. MATTHEWS
DESIGNED BY:	J. GRIGAS	SHEET	49 OF 52
EPSC PLAN SHEET			