

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	EROSION CONTROL	BRIDGE	FULL CE ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							300				300		LF	DURABLE 4 INCH YELLOW LINE, POLYUREA	646.414				
							206				206		LF	DURABLE 8 INCH WHITE LINE, POLYUREA	646.444				
							1				1		EACH	DURABLE LETTER OR SYMBOL, POLYUREA	646.494				
							430				430		SY	GEOTEXTILE FOR ROADBED SEPARATOR	649.11				
								40			40		SY	GEOTEXTILE FOR SILT FENCE	649.51				
								80			80		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
								30			30		SY	SODDING	651.30				
								5			5		CY	TOPSOIL	651.35				
								30			30		CY	VEHICLE TRACKING PAD	653.35				
								4			4		EACH	INLET PROTECTION DEVICE, TYPE I	653.40				
								110			110		LF	BARRIER FENCE	653.50				
							1				1		LS	TREE PROTECTION	656.85				
							6				6		SF	TRAFFIC SIGNS, TYPE A	675.20				
							30				30		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
							6				6		EACH	REMOVING SIGNS	675.50				
							1				1		EACH	ERECTING SALVAGED SIGNS	675.60				
							1				1		EACH	PULL BOX, STANDARD	678.25				
							1				1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50				
									47		47		CY	SPECIAL PROVISION (HIGH PERFORMANCE CONCRETE, RAPID SET)(FPQ)	900.608				
							66000				66000		DL	SPECIAL PROVISION (INCENTIVE/DISINCENTIVE) (N.A.B.I.)	900.615				
							4000				4000		DL	SPECIAL PROVISION (PARKING METER)(N.A.B.I.)	900.615				
							1				1		EACH	SPECIAL PROVISION (CPM SCHEDULE)	900.620				
							5				5		EACH	SPECIAL PROVISION (PARKING METER POST)	900.620				
							3				3		EACH	SPECIAL PROVISION (REMOVE PARKING METER POST)	900.620				
									128		128		LF	SPECIAL PROVISION (BRIDGE RAILING, TEXAS)(C412)	900.640				
							35				35		LF	SPECIAL PROVISION (PEDESTRIAN HAND RAILING)	900.640				
									85		85		LF	SPECIAL PROVISION (PRESTRESSED CONCRETE SOLID SLABS EXTERIOR)(18"x48")	900.640				
									467		467		LF	SPECIAL PROVISION (PRESTRESSED CONCRETE SOLID SLABS INTERIOR)(18"x39")	900.640				
									1		1		LS	SPECIAL PROVISION (CONSTRUCTION VIBRATION AND CRACK MONITORING)	900.645				
							1				1		LS	SPECIAL PROVISION (TRAFFIC CONTROL, ALL-INCLUSIVE)	900.645				
							1				1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, TYPE IVB)(N.A.B.I.)	900.650				
									1470		1470		SF	SPECIAL PROVISION (CONCRETE BRIDGE DECK SURFACE PREPARATION)	900.670				
							188				188		SF	SPECIAL PROVISION (REMOVE AND RESET BRICK PAVERS)	900.670				
							64		45		109		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, TYPE IVB)	900.680				

PROJECT NAME: WOODSTOCK VILLAGE
PROJECT NUMBER: BF 020-2(43)
FILE NAME: s13j280qs PLOT DATE: 09-AUG-2017
PROJECT LEADER: R. YOUNG DRAWN BY: S. COLEY
DESIGNED BY: S. COLEY CHECKED BY: W. LAMMER
QUANTITY SHEET 2 SHEET 8 OF 53