

# QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES				
										BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
										1		1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
										1075		1075		LB	STRUCTURAL STEEL	506.60				
										402		402		LF	REMOVAL OF EXISTING BRIDGE RAILING	525.10	-			
										1		1		EACH	PARTIAL REMOVAL OF STRUCTURE	529.20	-			
										412		412		LF	TREATED TIMBER CURB	616.35	-			
										25		25		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED	621.21	-			
										1		1		EACH	TERMINAL CONNECTOR FOR STEEL BEAM GUARDRAIL	621.53				
										25		25		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	-			
										40		40		HR	FLAGGERS	630.15	-			
											1	1		LS	FIELD OFFICE, ENGINEERS	631.10	-			
											1	1		LS	TESTING EQUIPMENT, PROTECTIVE COATINGS	631.18	-			
											3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-			
										1		1		LS	MOBILIZATION/DEMobilIZATION	635.11	-			
										1		1		LS	TRAFFIC CONTROL	641.10	-			
										4		4		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-			
										402		402		LF	SPECIAL PROVISION (BRIDGE RAILING, TRUSS)	900.640	-			
										1		1		LS	SPECIAL PROVISION (CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES)	900.645	-			
										1		1		LS	SPECIAL PROVISION (QC/QA CLEAN AND PAINT EXISTING STEEL STRUCTURES, BARE STEEL)	900.645	-			

PROJECT NAME: MONTPELIER  
 PROJECT NUMBER: BF BPNT (17)  
 FILE NAME: z13j290frm.dgn  
 PROJECT LEADER: T. KNIGHT  
 DESIGNED BY: T. KNIGHT  
 QUANTITY SHEET - QTY 1  
 PLOT DATE: 6/2/2014  
 DRAWN BY: L. BUXTON  
 CHECKED BY: T. KNIGHT  
 SHEET 3 OF 16

