



MESSAGES FOR PORTABLE CHANGEABLE MESSAGE SIGNS (PCMS)

STARTING 2 WEEK(S) PRIOR TO CLOSURE

PHASE 1	<b>BRIDGE CLOSED</b>
	<b>ON GRANITE ST</b>
PHASE 2	<b>XXXXXX - XXXXXX</b>
	<b>USE MAIN ST</b>
	<b>OR BARRE ST</b>

NOTES:

1. ALL COSTS OF INSTALLING, MAINTAINING, AND REMOVING THE SIGNS AND BARRICADES IN THIS TRAFFIC CONTROL PLAN AS NECESSARY TO MEET PROJECT CONDITIONS WILL BE INCIDENTAL TO ITEM 641.10, "TRAFFIC CONTROL". PCMS WILL BE PAID FOR SEPARATELY UNDER CONTRACT ITEM 641.15.
2. ALL TRAFFIC SIGNS SHALL CONFORM TO THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (MUTCD) 2009 EDITION.
3. "ROAD CLOSED" SIGNS SHALL BE MOUNTED AND MAINTAINED ON LIGHTED TYPE III BARRICADES.
4. TYPE III CONSTRUCTION BARRICADES SHALL BE PLACED SO AS TO PHYSICALLY EXCLUDE TRAFFIC FROM THE ENTIRE ROADWAY WIDTH OR AT THE DISCRETION OF THE ENGINEER.
5. WHERE POSSIBLE LOCATE DETOUR ROUTE MARKER ASSEMBLIES ADJACENT TO EXISTING ROUTE MARKER ASSEMBLIES.
6. SIGN SPACING IS FOR REFERENCE ONLY, FIELD ADJUSTMENTS WILL LIKELY BE NECESSARY, AS APPROVED BY THE ENGINEER.

NOT TO SCALE

PROJECT NAME: MONTPELIER  
PROJECT NUMBER: BF BPNT(17)

FILE NAME: z13j290de+our.dgn  
PROJECT LEADER: T. KNIGHT  
DESIGNED BY: D. DEBAIE  
TRAFFIC CONTROL SHEET - TCSI

PLOT DATE: 5/12/2014  
DRAWN BY: G.BARRETT  
CHECKED BY: E. ALLING  
SHEET 4 OF 16

