



COLOR: BLACK BORDER & SYMBOL
WITH ORANGE (RETROREFLECTIVE) BACKGROUND

TRAFFIC SIGN NOTES

1. ALL SIGN LETTERING, DIGITS, ARROWS, AND DESIGN OF SYMBOLS FOR SIGNS REFERENCED IN THESE PLANS SHALL CONFORM WITH THE LATEST EDITION OF "STANDARD ALPHABET FOR HIGHWAY SIGNS AND PAVEMENT MARKINGS" AS ADOPTED BY THE U.S. DEPARTMENT OF TRANSPORTATION AND THE FEDERAL HIGHWAY ADMINISTRATION (FHWA) UNLESS OTHERWISE DETAILED WITHIN THESE PLANS.
2. ALL COLORS SHALL CONFORM WITH THE STANDARD COLORS ADOPTED BY THE AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO) AND APPROVED BY FHWA UNLESS OTHERWISE NOTED.
3. UNLESS OTHERWISE DETAILED ON THE PLANS, ALL SIGN BASE MATERIALS SHALL BE FLAT SHEET ALUMINUM WITH THE FOLLOWING MINIMUM THICKNESSES:

SIZES			36" X 12"	
	24" X 10"	36" X 15"		
	24" X 12"	42" X 12"		
	30" X 12"	48" X 12"		
	24" X 18"	36" X 18"		
	24" X 24"	54" X 12"	48" X 18"	
	24" X 30"	36" X 24"	48" X 24"	
	9" X 12"	30" X 15"	30" X 42"	48" X 30"
	12" X 12"	30" X 18"	36" X 36"	48" X 42"
	18" X 18"	30" X 30"	36" X 48"	48" X 48"
	21" X 15"	30" X 42"	36" X 54"	48" X 60"
THICKNESS	0.080"	0.080"	0.100"	0.125"



PROJECT NAME: MONTPELIER
PROJECT NUMBER: BF BPNT (17)

FILE NAME: z13j290Sign_details.dgn PLOT DATE: 5/12/2014
PROJECT LEADER: T. KNIGHT DRAWN BY: D. DRAPER
DESIGNED BY: D. DRAPER CHECKED BY: E. ALLING
TRAFFIC SIGN SHEET - TSS 1 SHEET 5 OF 16