

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
								ROADWAY	EROSION CONTROL	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								98		98		TON	AGGREGATE SHOULDERS	402.12	0.5			
								864		864		LF	REMOVAL OF EXISTING BRIDGE RAILING	525.10	-			
								684		684		LF	BRIDGE RAILING REPAIR, TYPE II	525.55	-			
								160		160		LF	BRIDGE RAILING REPAIR, TYPE III	525.60	-			
								40		40		HR	POWER GRADER RENTAL	608.15	EST			
								40		40		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST			
								40		40		HR	POWER BROOM RENTAL, TYPE I	608.30	EST			
								40		40		HR	TRUCK RENTAL	608.37	EST			
									550	550		CY	STONE FILL, TYPE I	613.10	EST			
								41500		41500		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	7			
								14500		14500		LF	STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.205	12.5			
								200		200		LF	STEEL BEAM GUARDRAIL, GALVANIZED/NESTED	621.206	37.5			
								50		50		LF	STEEL BEAM GUARDRAIL, GALVANIZED/NESTED W/8 FEET POSTS	621.207	-			
								2077		2077		LF	BOX BEAM GUARDRAIL	621.30	-			
								7		7		EACH	MANUFACTURED TERMINAL SECTION, FLARED	621.50	-			
								4		4		EACH	TERMINAL CONNECTOR FOR STEEL BEAM GUARDRAIL	621.53	-			
								223		223		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-			
								38		38		EACH	GUARDRAIL APPROACH SECTION, GALV HD STEEL BEAM	621.737	-			
								56334		56334		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	-			
								40		40		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST			
								3000		3000		HR	FLAGGERS	630.15	EST			
								1		1		LS	MOBILIZATION/DEMobilIZATION	635.11	-			
								1		1		LS	TRAFFIC CONTROL	641.10	-			
									30	30		LB	SEED	651.15	EST			
									30	30		LB	FERTILIZER	651.18	EST			
									4	4		TON	AGRICULTURAL LIMESTONE	651.20	EST			
									4	4		TON	HAY MULCH	651.25	EST			
									100	100		SY	TEMPORARY EROSION MATTING	653.20	EST			
								233		233		EACH	DELINEATOR WITH STEEL POST	676.10	-			
								233		233		EACH	REMOVAL OF EXISTING DELINEATOR	676.12	-			
								1		1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-			
								5		5		EACH	SPECIAL PROVISION (MANUFACTURED TERMINAL SYSTEM, X-LITE TANGENT)	900.620	-			

PROJECT NAME: STATEWIDE  
 PROJECT NUMBER: HES GARD(2)  
 FILE NAME: d13k342frm.dgn PLOT DATE: 27-MAR-2015  
 PROJECT LEADER: B. MARTIN DRAWN BY: M. GAMELIN  
 DESIGNED BY: M. GAMELIN CHECKED BY: A. KEMPTON  
 QUANTITY SHEET 1 SHEET 4 OF 21