

CONVENTIONAL SYMBOLS

GENERAL INFORMATION

SYMBOLGY LEGEND NOTE

THE SYMBOLGY ON THIS SHEET IS INTENDED TO COVER STANDARD CONVENTIONAL SYMBOLGY. THE SYMBOLGY IS USED FOR EXISTING & PROPOSED FEATURES WITH HEAVIER LINEWEIGHT, IN COMBINATION WITH PROJECT ANNOTATION, AS NOTED ON PROJECT PLAN SHEETS. THIS LEGEND SHEET COVERS THE BASICS. SYMBOLGY ON PLANS MAY VARY, PLAN ANNOTATIONS AND NOTES SHOULD BE USED TO CLARIFY AS NEEDED.

R.O.W. ABBREVIATIONS (CODES) & SYMBOLS

POINT	CODE	DESCRIPTION
	CH	CHANNEL EASEMENT
	CONST	CONSTRUCTION EASEMENT
	CUL	CULVERT EASEMENT
	D&C	DISCONNECT & CONNECT
	DIT	DITCH EASEMENT
	DR	DRAINAGE EASEMENT
	DRIVE	DRIVEWAY EASEMENT
	EC	EROSION CONTROL
	I&M	INSTALL & MAINTAIN EASEMENT
	LAND	LANDSCAPE EASEMENT
	R&RES	REMOVE & RESET
	R&REP	REMOVE & REPLACE
	SR	SLOPE RIGHT
	UE	UTILITY EASEMENT
	(P)	PERMANENT EASEMENT
	(T)	TEMPORARY EASEMENT
■	BNDNS	BOUND SET
□	BNDNS	BOUND TO BE SET
●	IPNS	IRON PIN SET
⊙	IPNS	IRON PIN TO BE SET
⊠	CALC	EXISTING ROW POINT
○	PROW	PROPOSED ROW POINT
[LENGTH]		LENGTH CARRIED ON NEXT SHEET

COMMON TOPOGRAPHIC POINT SYMBOLS

POINT	CODE	DESCRIPTION
⊕	APL	BOUND APPARENT LOCATION
□	BM	BENCH MARK
□	BND	BOUND
⊠	CB	CATCH BASIN
⊕	COMB	COMBINATION POLE
⊠	DITHR	DROP INLET THROATED DNC
⊕	EL	ELECTRIC POWER POLE
⊙	FPOLE	FLAGPOLE
○	GASFIL	GAS FILLER
○	GP	GUIDE POST
⊗	GSO	GAS SHUT OFF
⊙	GUY	GUY POLE
⊙	GUYW	GUY WIRE
⊗	GV	GATE VALUE
⊗	H	TREE HARDWOOD
△	HCTRL	CONTROL HORIZONTAL
△	HVCTRL	CONTROL HORIZ. & VERTICAL
⊕	HYD	HYDRANT
⊕	IP	IRON PIN
⊕	IPIPE	IRON PIPE
⊕	LI	LIGHT - STREET OR YARD
⊕	MB	MAILBOX
○	MH	MANHOLE (MH)
□	MM	MILE MARKER
⊙	PM	PARKING METER
⊕	PMK	PROJECT MARKER
⊕	POST	POST STONE/WOOD
⊕	RRSIG	RAILROAD SIGNAL
⊕	RRSL	RAILROAD SWITCH LEVER
⊕	S	TREE SOFTWOOD
⊕	SAT	SATELLITE DISH
⊕	SHRUB	SHRUB
⊕	SIGN	SIGN
⊕	STUMP	STUMP
⊕	TEL	TELEPHONE POLE
⊕	TIE	TIE
⊕	TSIGN	SIGN W/DOUBLE POST
⊕	VCTRL	CONTROL VERTICAL
⊕	WELL	WELL
⊕	WSO	WATER SHUT OFF

THESE ARE COMMON VAOT SURVEY POINT SYMBOLS FOR EXISTING FEATURES, ALSO USED FOR PROPOSED FEATURES WITH HEAVIER LINEWEIGHT, IN COMBINATION WITH PROPOSED ANNOTATION.

PROPOSED GEOMETRY CODES

CODE	DESCRIPTION
PC	POINT OF CURVATURE
PI	POINT OF INTERSECTION
CC	CENTER OF CURVE
PT	POINT OF TANGENCY
PCC	POINT OF COMPOUND CURVE
PRC	POINT OF REVERSE CURVE
POB	POINT OF BEGINNING
POE	POINT OF ENDING
STA	STATION PREFIX
AH	AHEAD STATION SUFFIX
BK	BACK STATION SUFFIX
D	CURVE DEGREE OF (100FT)
R	CURVE RADUIS OF
T	CURVE TANGENT LENGTH
L	CURVE LENGTH OF
E	CURVE EXTERNAL DISTANCE

UTILITY SYMBOLGY

UNDERGROUND UTILITIES

— UT —	TELEPHONE
— UE —	ELECTRIC
— UC —	CABLE (TV)
— — —	ELECTRIC+CABLE
— — —	ELECTRIC+TELEPHONE
— — —	CABLE+TELEPHONE
— — —	ELECTRIC+CABLE+TELEP.
— G —	GAS LINE
— W —	WATER LINE
— S —	SANITARY SEWER (SEPTIC)

ABOVE GROUND UTILITIES (AERIAL)

— T —	TELEPHONE
— E —	ELECTRIC
— — —	CABLE (TV)
— — —	ELECTRIC+CABLE
— — —	ELECTRIC+TELEPHONE
— AER E&T —	ELECTRIC+TELEPHONE
— — —	CABLE+TELEPHONE
— — —	ELECTRIC+CABLE+TELEP.
— — —	UTILITY POLE GUY WIRE

PROJECT CONSTRUCTION SYMBOLGY

PROJECT DESIGN & LAYOUT SYMBOLGY

— CZ —	CLEAR ZONE
— — —	PLAN LAYOUT MATCHLINE

PROJECT CONSTRUCTION FEATURES

△	TOP OF CUT SLOPE
○	TOE OF FILL SLOPE
⊕	STONE FILL
— — —	BOTTOM OF DITCH CL
— — —	CULVERT PROPOSED
— — —	STRUCTURE SUBSURFACE
PDF	PROJECT DEMARCATION FENCE
— — —	BARRIER FENCE
XXXXXX	TREE PROTECTION ZONE (TPZ)
///	STRIPING LINE REMOVAL
~~~~~	SHEET PILES

## CONVENTIONAL BOUNDARY SYMBOLGY

### BOUNDARY LINES

— TOWN LINE —	TOWN BOUNDARY LINE
— COUNTY LINE —	COUNTY BOUNDARY LINE
— STATE LINE —	STATE BOUNDARY LINE
— — —	PROPOSED STATE R.O.W. (LIMITED ACCESS)
— — —	PROPOSED STATE R.O.W.
— — —	STATE ROW (LIMITED ACCESS)
— — —	STATE ROW
— — —	TOWN ROW
— — —	PERMANENT EASEMENT LINE (P)
— — —	TEMPORARY EASEMENT LINE (T)
— — —	SURVEY LINE
— P —	PROPERTY LINE (P/L)
SR	SLOPE RIGHTS
6f	6F PROPERTY BOUNDARY
4f	4F PROPERTY BOUNDARY
HAZ	HAZARDOUS WASTE

## EPSC LAYOUT PLAN SYMBOLGY

### EPSC MEASURES

○●●●○●●●○	FILTER CURTAIN
— — —	SILT FENCE
— — —	SILT FENCE WOVEN WIRE
— — —	CHECK DAM
— — —	DISTURBED AREAS REQUIRING RE-VEGETATION
— — —	EROSION MATTING

## ENVIRONMENTAL RESOURCES

— — —	WETLAND BOUNDARY
— — —	RIPARIAN BUFFER ZONE
— — —	WETLAND BUFFER ZONE
— — —	SOIL TYPE BOUNDARY
— T&E —	THREATENED & ENDANGERED SPECIES
— HAZ —	HAZARDOUS WASTE AREA
— AG —	AGRICULTURAL LAND
— HABITAT —	FISH & WILDLIFE HABITAT
— FLOOD PLAIN —	FLOOD PLAIN
— OHW —	ORDINARY HIGH WATER (OHW)
— — —	STORM WATER
— — —	USDA FOREST SERVICE LANDS
— — —	WILDLIFE HABITAT SUIT/CONN

## ARCHEOLOGICAL & HISTORIC

— ARCH —	ARCHEOLOGICAL BOUNDARY
— HISTORIC DIST —	HISTORIC DISTRICT BOUNDARY
— HISTORIC —	HISTORIC AREA
(H)	HISTORIC STRUCTURE

## CONVENTIONAL TOPOGRAPHIC SYMBOLGY

### EXISTING FEATURES

— — —	ROAD EDGE PAVEMENT
— — —	ROAD EDGE GRAVEL
— — —	DRIVEWAY EDGE
— — —	DITCH
— — —	FOUNDATION
— — —	FENCE (EXISTING)
— — —	FENCE WOOD POST
— — —	FENCE STEEL POST
— — —	GARDEN
— — —	ROAD GUARDRAIL
— — —	RAILROAD TRACKS
— — —	CULVERT (EXISTING)
— — —	STONE WALL
— — —	WALL
— — —	WOOD LINE
— — —	BRUSH LINE
— — —	HEDGE
— — —	BODY OF WATER EDGE
— — —	LEDGE EXPOSED

PROJECT NAME: WATERBURY AREA  
PROJECT NUMBER: STP WKZN(9) C/2

FILE NAME: t13k670frm.dgn  
PROJECT LEADER: P. COBURN  
DESIGNED BY: I. DEGUTIS  
CONVENTIONAL SYMBOLGY LEGEND SHEET

PLOT DATE: 10/21/2014  
DRAWN BY: B. GROSE  
CHECKED BY: M. LACROIX  
SHEET 2 OF 13