



NEMA M-34 Traffic Control Cabinet



Features

- Meets NEMA standards
- Pole mounted
- Constructed of 0.125" thick aluminum
- "C" mounting channels on side and back walls for mounting shelves and panels
- 3-point latching mechanism of zinc plated steel
- Stainless steel door handle designed for padlock
- Stainless steel door hinge
- Optional Lifting Ears



Highway Tech Signal Equipment Sales, Inc.
8 Gardiner Road / P.O. Box 1209
Sabattus, ME 04280
Tel. (207) 375-8248
Fax (207) 375-8279

SPECIFICATIONS:

Outside dimensions:	50" H x 34" W x 18" deep
Mounting Pattern:	Pole Mount
Material:	Aluminum (.125" thick)
Finish:	Bare or Painted
Mounting:	Pole Mounted
Locking System:	3-point locking system with Corbin #2 lock
Door Stops:	Three position bar stop at bottom of door
Ventilation:	Pleated fiber filter in door, fan with thermostatic control
Light:	Incandescent or optional flourescent, door switch activated

Technology That Moves America

Naztec, Inc. • 820 Park Two Drive • Sugar Land, Texas 77478 • Phone (281) 240-7233 • Fax (281) 240-7238

Email: naztec@naztec.com • <http://www.naztec.com>