

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	EROSION CONTROL	LANDSCAPING	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
									4		4		EACH	EVERGREEN TREES (PICEA GLAUCA)(B&B, 10'-12' O.C., SPRING PLANTING)	656.20	--			
									2		2		EACH	DECIDUOUS TREES (ACER FREMANII "AUTUMN BLAZE")(B&B, 5' MIN BRANCH HEIGHT, SPRING PLANTING)	656.30	--			
									1		1		EACH	DECIDUOUS TREES (SYRINGA RETICULATA, TREE FORM)(B&B, NO MIN BRANCH HEIGHT, SPRING PLANTING)	656.30	--			
									1		1		MGAL	LANDSCAPE WATERING	656.65	EST.			
							21				21		EACH	REMOVING SIGNS	675.50	--			
							21				21		EACH	ERECTING SALVAGED SIGNS	675.60	--			
							10				10		EACH	SETTING SALVAGED POSTS	675.61	--			
							2				2		EACH	REMOVING AND RESETTING LIGHT POLE	679.25	--			
							1				1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	--			
							6				6		EACH	SPECIAL PROVISION (LUMINAIRE, LED RETROFIT)	900.620	--			
							301				301		LF	SPECIAL PROVISION (VERTICAL GRANITE CURB, MOUNTABLE)	900.640	6			
							1				1		LS	SPECIAL PROVISION (TEMPORARY ROADWAY WIDENING)	900.645	--			
							1				1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY)(N.A.B.I.)	900.650	--			
							1				1		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT)(N.A.B.I.)	900.650	--			
							89				89		SY	SPECIAL PROVISION (PORTLAND CEMENT CONCRETE ISLAND TREATMENT, 8 INCH)	900.675	2.6			
							512				512		SY	SPECIAL PROVISION (STAMPED CONCRETE APRON, 8 INCH)	900.675	5			
							616				616		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680	12			

PROJECT NAME: HYDE PARK
PROJECT NUMBER: HES 030-2(34)
FILE NAME: t14b104frm.dgn
PROJECT LEADER: P. COBURN
DESIGNED BY: M. BOGACZYK
QUANTITY SHEET 2
PLOT DATE: 11/24/2015
DRAWN BY: M. BOGACZYK
CHECKED BY: M. LACROIX
SHEET 8 OF 26