DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION SIGN DETAIL SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
NB BARTON TH-3							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
NB	2.869	A	W1-2R				RIGHT CURVE						1		X											6-14-18			
		A	W13-1p				30 M.P.H. (PLAQUE)						1																
		A					SNOW DRIFTS						1																
		A		30	30			6.25								1		14.50 X								HINGED / FOLDING		26	
NB	3.192	A					30 M.P.H. AHEAD						1		X														
NB	3.433	A	R2-1				SPEED LIMIT 30						1		X											6-15-18			
		A	R2-1	30	36			7.50								1		14.50 X									X		
							SHEET TOTALS	13.75	0.00	0	0	0	5	0	0	2		29.0 ~~30.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	77.5	0.0	4	3	3	13	0	0	13		195.0		0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: STATEWIDE-NORTH REGION
PROJECT NUMBER: STP HRRR(22)

FILE NAME: z14k100tssbarton TH3 NB.xls
PROJECT MANAGER: K. RUTTER
DESIGNED BY: R. SHEDD
PLOT DATE: 5/5/2017
DRAWN BY: R. SHEDD
CHECKED S. GOODWIN

BARTON TH-3 NORTHBOUND 3