





DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS			EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION				
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN		REMOVE	1.75	2.00	2.50	FOUNDATION	3.00	3.50			4.00	5.00	SHSM	SIGN DETAIL SHEET #	STANDARD SHEET #
																	(LB / FT)				(LB / FT)								
SB BARTON TH-3							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN															"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK							
SB	3.079	F	W1-2L				LEFT CURVE																						
		F	W13-1p				30 M.P.H. (PLAQUE)																						
		F					SNOW DRIFTS																						
		F		30	30			6.25																	26				
		F		30	30																								
SB	3.035 - 2.987	F		6	8		INSTALL (4) NEW DELINEATOR POSTS																INSTALL (8) TYPE II 6"x8" WHITE DELINEATORS BACK TO BACK ON 4 NEW POSTS; INSTALL THE FIRST POST AT MP 2.987, 50 FT ± SOUTH OF UTILITY POLE 36 AT MP 2.996, THEN EVERY 85 FT ±, SEE SHEET 9						
SB	2.942						EMPTY POST																PAID FOR AS ITEM 676.12, REMOVAL OF EXISTING DELINEATOR, SEE SHEET 7						
SB	2.745	F	W13-1p				30 M.P.H. (PLAQUE)																						
		F	R2-1	24	30			5.00																	X				
		F																											
SB	2.627	F	VW-133L	30	30			6.25															INSTALL 143 FT ± NORTH OF POST PROPOSED TO BE REMOVED AT MP 2,600						
		F																					6-15-18						
SB	2.600						EMPTY POST																PAID FOR AS ITEM 676.12, REMOVAL OF EXISTING DELINEATOR, SEE SHEET 7						
		F																							7				
SB	2.408	F	W11-2				PEDESTRIAN SYMBOL																						
		F																											
SB	2.323	F	VW-133L	30	30			6.25															INSTALL 10 FT ± SOUTH OF UP 9 AT MP 2,325						
		F																											
SB	2.021	F	W1-2R				RIGHT CURVE																						
		F																											
		F	W13-1p				30 M.P.H. PLAQUE																						
		F																											
SIGN SUMMARY SHEET							SHEET TOTALS	23.75	0.00	0	0	0	7	0	0	4								PROJECT NAME: STATEWIDE-NORTH REGION					
																							PROJECT NUMBER: STP HRRR(22)						
																							FILE NAME: z14k100tssbarton TH3 SB.xls PLOT DATE: 5/5/2017						
																							PROJECT MANAGER: K. RUTTER DRAWN BY: R. SHEDD						
																							DESIGNED BY: R. SHEDD CHECKED: S. GOODWIN						
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	63.6	0.0	5	3	3	12	0	0	14								BARTON TH-3 SOUTHBOUND 1 SHEET 46 OF 255					

4 DEL.

6-15-18

6-14-18

6-15-18

MISSING

MISSING