DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION SIGN DETAIL SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
NB BURLINGTON VT 127							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
NB	2.980	A	R2-5A				REDUCED SPEED AHEAD						1		X													
NB	2.999	A	W3-5	36	36		4-30-18	9.00								2		14.50 X ~~15.50~~								X		
NB	3.043	A					LANES DIVIDE 500 FEET						1		X													
		A	VR-921L	30	30		4-30-18	6.25								2		15.25 X 16.00										E-145A
		A	W16-2aP	30	18		4-30-18	3.75																		X		
NB	3.082	A	R2-1				4-30-18 SPEED LIMIT 35						1		X													
		A	R2-1	30	36			7.50								1		14.00 X								INSTALL SIGN ON ITS OWN POST 10 FT IN FRONT OF LUMINAIRE #L5	X		
NB	3.129	A	W3-3				4-30-18 SIGNAL AHEAD						1		X													
		A	W3-3	30	30			6.25								1		14.00 X									X		
NB	3.168	A	VD1-1				UP MALLETS BAY						1		X													
		A	VD1-1				<-- PLATTSBURG AVE						1															
		A	VD1-1				<-- NORTH AVE						1															
		A	M3-1				NORTH						1															
		A	M1-5				VT 127						1															
		A	M6-3				UP ARROW						1															
SIGN SUMMARY SHEET							SHEET TOTALS	32.75	0.00	0	0	0	10	0	0	6		~~89.25~~ ~~90.0~~		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	98.4	0.0	0	0	0	17	0	0	14		180.0		2	216.6							

PROJECT NAME: **STATEWIDE-NORTH REGION**
PROJECT NUMBER: **STP HRRR(22)**
FILE NAME: **z14K100tssburlington VT127** PLOT DATE: **5/5/2017**
PROJECT MANAGER: **K. RUTTER** DRAWN BY: **R. SHEDD**
DESIGNED BY: **R. SHEDD** CHECKED **S. GOODWIN**
BURLINGTON VT127 NORTHBOUND 1 SHEET **54** OF **255**