| DIRECTION | MILEPOINT | LOCATION CODE (SHEET 4) | SIGN CODE | WIDTH (IN) | HEIGHT (IN) | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXIST POST RETAIN | EXIST POST REMOVE | NUMBER OF NEW POSTS | SQUARE STEEL (IN) 1.75 (LB / FT) 1.88 | SQUARE STEEL (IN) 2.00 (LB / FT) 2.42 | SQUARE STEEL (IN) 2.50 (LB / FT) 3.35 | TUBULAR STEEL Ø (IN) FOUNDATION | TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60 | TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00 | TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80 | TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60 | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL LOCATION SHSM | SIGN DETAIL LOCATION SIGN DETAIL SHEET # | SIGN DETAIL LOCATION STANDARD SHEET # |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **SB CABOT TH-1** | | | | | | | FY-FLUORESCENT YELLOW<br>FYG-FLUORESCENT YELLOW GREEN | | | | | | | | | | | | | | | | | | | "SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK | | | |
| SB | 3.775 | F | W7-1 | | | | HILL WARNING | | | | | | 1 | | X | | | | | | | | | | | 6-5-18 | | | |
| SB | 3.775 | F | W7-1 | 30 | 30 | | | 6.25 | | | | | | | | 1 | | 14.25<br>X | | | | | | | | X | | |
| SB | 3.514 | F | | | | | SPEED LIMIT 30 | | | 1 | | | | 1 | | | | | | | | | | | | 6-7-18 | | | |
| SB | 3.514 | F | | | | | YOUR SPEED (RADAR SPEED DETECTOR) | | | 1 | | | | | | | | | | | | | | | | | | | |
| SB | 3.442 | GH | D3-1 | | | | RTE 215 N | | | 1 | | | | X | | | | | | | | | | | | | | | |
| | | EF | D3-1 | | | | S WALDEN RD | | | 1 | | | | X | | | | | | | | | | | | | | | |
| SB | 3.442 | G | R1-2 | 36 | 36 | | | 3.90 | | | | | 1 | X | | 1 | | 14.25<br>X | | | | | | | 36"x36"x36" | | X | |
| SB | 3.428 | H | D3-1 | | | | ROUTE 215 N | | | | | | 1 | | X | | | | | | | | | | | | | | |
| | | H | D3-1 | | | | MAINT ST - 215 | | | | | | 1 | | | | | | | | | | | | | | | | |
| | | H | R1-1 | | | | STOP | | | | | | 1 | | | | | | | | | | | | | | | | |
| | | H | R1-1 | 30 | 30 | | | 6.25 | | | | | | | | 1 | | 15.00<br>X | | | | | | | | X | | |
| SB | 3.428 | GH | D3-1 | 36 | 12 | | Main St | 3.00 | | | | | | | | 2 | | 12.75<br>X<br>~~13.25~~ | | | | | | | | | 2 | |
| | | EF | D3-1 | 52 | 12 | | S Walden Rd | 4.33 | | | | | | | | | | | | | | | | | | | 2 | |
| SB | 3.378 | F | S1-1 | 36 | 36 | FYG | | 9.00 | | | | | | | | 2 | | 13.75<br>X<br>~~13.75~~ | | | | | | | | | X | |
| | | F | S4-3P | 24 | 8 | FYG | | 1.33 | | | | | | | | | | | | | | | | | | | X | |
| **SIGN SUMMARY SHEET** | | | | | | | SHEET TOTALS | 34.07 | 0.00 | 4 | 0 | 0 | ~~5~~ 4 | 1 | 0 | 7 | | ~~105.0~~ 97.0 | | 0 | 0.0 | 0.0 | 0.0 | 0.0 | | | | | |
| | | | | | | | | SF | SF | EA | EA | EA | EA | EA | EA | EA | | FT | | EA | LB | LB | LB | LB | | | | | |
| VERMONT AGENCY OF TRANSPORTATION | | | | | | | TOWN DIRECTIONAL TOTALS | 262.7 | 0.0 | 20 | 2 | 2 | 38 | 1 | 0 | 48 | | 720.0 | | 0 | 0.0 | | | | | | | | |

PROJECT NAME: STATEWIDE-NORTH REGION
PROJECT NUMBER: STP HRRR(22)

FILE NAME: z14k100tsscabot TH1 SB
PROJECT MANAGER: K. RUTTER
DESIGNED BY: R. SHEDD
CABOT TH-1 SOUTHBOUND 2

PLOT DATE: 5/5/2017
DRAWN BY: R. SHEDD
CHECKED S. GOODWIN