DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) (LB / FT) 1.75 / 1.88	2.00 / 2.42	2.50 / 3.35	TUBULAR STEEL Ø (IN) (LB / FT) FOUNDATION	3.00 / 7.60	3.50 / 9.00	4.00 / 10.80	5.00 / 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL SHEET #	STANDARD SHEET #
SB CABOT TH-1							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
SB	3.000	F					(CONT.) NEIGHBORHOOD WATCH			1																6-7-18			
SB	2.993	F	R3-9cP	30	12			2.50																		INSTALL 10 FT ± NORTH OF UTILITY POLE GMP/82	X		
		F	R8-3	24	24			4.00								1		14.00 X									X		
SB	2.960	F	R3-9dP	30	12			2.50																		6-8-18 INSTALL 10 FT ± NORTH OF UTILITY POLE GMP/81	X		
		F	R8-3	24	24			4.00								1		14.25 X									X		
SB	2.958	G	R1-1				STOP						1													STOP SIGN ON UTILITY POLE			
SB	2.912	F	W11-2				PEDESTRIAN			1				X															
		F	W16-7pL				RIGHT DOWN ARROW			1																			
SB	2.550	F	M3-3				SOUTH			1				X															
		F	M1-5				ROUTE 215 S			1																			
SB	2.447	F	R2-1				SPEED LIMIT 35			1				X															
SB	2.424	F	W5-2				NARROW BRIDGE			1				X															
SB	2.405	F	W1-1L				LEFT TURN			1				X															
		F	W13-1p				30 MPH (PLAQUE)			1																			
SB	2.385	F	OM3-R				OBJECT MARKER			1				X															
							SHEET TOTALS	13.00	0.00	10	0	0	1	0	0	2		28.25 ~~30.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	262.7	0.0	20	2	2	38	1	0	48		720.0		0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE-NORTH REGION**
PROJECT NUMBER: **STP HRRR(22)**

FILE NAME: **z14k100tsscabot TH1 SB**
PROJECT MANAGER: **K. RUTTER**
DESIGNED BY: **R. SHEDD**
CABOT TH-1 SOUTHBOUND 5

PLOT DATE: **5/5/2017**
DRAWN BY: **R. SHEDD**
CHECKED **S. GOODWIN**