DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION SIGN DETAIL SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SB DANVILLE TH-3							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
SB	2.816	F	R2-1				SPEED LIMIT 30						1		X											5-21-18			
		F	R2-1	24	30			5.00								1		14.50 X									X		
SB	2.669	F	R2-1				END SPEED 30						1		X														
		F	R2-1	24	30			5.00								1		14.50 X									X		
SB	2.526 - 2.478	F		6	8		INSTALL (4) NEW DELINEATOR POSTS																			INSTALL (8) TYPE II 6"x8' WHITE DELINEATORS BACK TO BACK ON 4 NEW POSTS; INSTALL THE FIRST POST AT MP 2.526, 755FT ± SOUTH OF EXISTING SIGN, THEN EVERY 85 FT ±, SEE SHEET 9			
SB	2.271	F	W1-2R	30	30			6.25								1		14.75 X									INSTALL 470 FT ± NORTH OF UTILITY POLE 19/38-01	X		
SB	2.075	F		6	8		INSTALL (1) NEW DELINEATOR POST																			5-19-18 INSTALL (1) TYPE II 6"X8" WHITE DELINEATOR ON 1 NEW POST; INSTALL THE POST AT MP 2.075, 560 FT ± SOUTH OF NORTHBOUND UTILITY POLE AT MP 2.182, SEE SHEET 9			
SB	1.992	E		6	8		INSTALL (1) NEW DELINEATOR POST																			INSTALL (1) TYPE II 6"X8" WHITE DELINEATOR ON 1 NEW POST; INSTALL THE POST AT MP 1.992, 1,000 FT ± SOUTH OF NORTHBOUND UTILITY POLE AT MP 2.182, SEE SHEET 9			
SB	1.664	F	R2-5A				REDUCED SPEED AHEAD						1		X														
SB	1.646	F	W3-5	36	36			9.00								2		14.50 X ~~15.00~~									INSTALL 95 FT ± SOUTH OF EXISTING SIGN AT MP 1.664	X		
SB	1.587	F	R2-1				SPEED LIMIT 35						1		X														
		F	R2-1	30	36			7.50								1		14.50 X							6 DEL.			X		
SIGN SUMMARY SHEET							SHEET TOTALS	32.75	0.00	0	0	0	4	0	0	6		~~87.75~~ ~~90.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	215.6	0.0	6	0	0	19	0	0	34		510.0		0	0.0								

PROJECT NAME: **STATEWIDE-NORTH REGION**
PROJECT NUMBER: **STP HRRR(22)**

FILE NAME: **z14k100tssdanvilleTH3 SB.xls**
PROJECT MANAGER: **K. RUTTER**
DESIGNED BY: **R. SHEDD**
DANVILLE TH-3 SOUTHBOUND 2

PLOT DATE: **5/5/2017**
DRAWN BY: **R. SHEDD**
CHECKED **S. GOODWIN**
SHEET **80** OF **255**