DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION SIGN DETAIL SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
NB HINESBURG TH-9							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
NB	0.036	A	VR-017				LLL 55,000 LBS						1		X											5-2-18			
		A	VR-017	24	30			5.00								1			15.75 X							~~SLIP BASE REQUIRED~~ SEE SHEET 9			T-70
		A	R2-1	30	36			7.50																		X		
NB	0.050	A	R2-5A				REDUCED SPEED AHEAD						1	X															
NB	0.095	A	R2-1				SPEED LIMIT 40						1	X															
NB	0.547	A	N/A	6	8		INSTALL (1) NEW DELINEATOR POST																			INSTALL (1) TYPE II 6"X8" WHITE DELINEATORS ON 1 NEW POST, SEE SHEET 9			
NB	0.583 - 0.595	A					REMOVE (3) DELINEATORS AND POSTS								X											PAID FOR AS ITEM 676.12, REMOVAL OF EXISTING DELINEATOR, SEE SHEET 7			
NB	0.583 - 0.595	A		4	4		INSTALL (3) NEW DELINEATOR POSTS																			INSTALL (3) 4"x4" WHITE DELINEATORS ON 3 NEW POSTS; INSTALL THE FIRST POST AT MP 0.583, 65 FT± SOUTH OF LINCOLN HILL RD, THEN EVERY 40 FT±, SEE SHEET 9			
NB	0.595	C	VR-017	24	30			5.00								1			14.75 X							5-3-18 INSTALL 50 FT ± FROM NORT RD ON LINCOLN HILL RD			T-70
		C	R2-1	24	30			5.00																		~~SLIP BASE REQUIRED~~ SEE SHEET 9	X		
NB	0.595	C	R2-5A				REDUCED SPEED AHEAD						1		X											REMOVE SIGNS LOCATED APPR 75 FT FROM NORTH RD ON LINCOLN HILL RD			
		C	VR-017				LLL 24,000 LBS						1																
NB	0.595	C	R2-1				SPEED LIMIT 30						1		X										4 DEL. 3 DEL. REM.	REMOVE SIGN LOCATED APPR 100 FT FROM NORTH RD ON LINCOLN HILL RD			
SIGN SUMMARY SHEET							SHEET TOTALS	22.50	0.00	0	0	0	6	0	0	2	~~30.0~~ 30.50			0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT			EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	93.1	0.0	4	0	0	16	0	0	16	240.0			0	0.0								

PROJECT NAME: **STATEWIDE-NORTH REGION**
PROJECT NUMBER: **STP HRRR(22)**

FILE NAME: **z14k100tsshinesbura TH9 NE** PLOT DATE: **5/5/2017**
PROJECT MANAGER: **K. RUTTER** DRAWN BY: **R. SHEDD**
DESIGNED BY: **R. SHEDD** CHECKED **S. GOODWIN**
HINESBURG TH-9 NORTHBOUND 1 SHEET **111** OF **255**