DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION SIGN DETAIL SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
NB HYDE PARK TH-1							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
NB	2.358	B	W1-6				LARGE ARROW RIGHT			1				X												5-9-18			
NB	2.362	B	R1-1				STOP			1				X															
NB	2.407	AB	D3-1				BROOK RD						1		X														
		AB	D3-1	40	12		Brook Rd	3.33								1		10.75 X									10		
NB	2.407	D	R1-1				STOP						1		X														
		D	R1-1	30	30		STOP	6.25								1		12.50 X									X		
NB	2.430	A	W1-1L	30	30			6.25								1		15.50 X								INSTALL 120 FT ± NORTH OF EXISTING SIGN AT MP 2.407	X		
		A	W13-1p	18	18		25 MPH	2.25																			X		
NB	2.450	A	W1-6	48	24			8.00								2		13.00 X ~~12.75~~								INSTALL 105 FT ± NORTH OF PROPOSED SIGN AT MP 2.430	X		
NB	2.451	B	W1-6	48	24			8.00								2		12.75 X ~~13.00~~									X		
NB	3.776	D	R1-2				YIELD						1		X											5-11-18			
		AB	D3-1	42	12		Center Rd	3.50								1		15.50 X								MOUNT CENTER RD PERP ON TOP OF YIELD SIGN		10	
		D	R1-2	36	36		YIELD	3.90																			X		
NB	3.776	D	W3-2	30	30			6.25								1		13.00 X								INSTALL ON CENTER RD 400 FT FROM CENTERVILLE RD	X		
SIGN SUMMARY SHEET							SHEET TOTALS	47.73	0.00	2	0	0	3	0	0	9		~~135.0~~ 118.75		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	153.2	0.0	10	0	0	20	0	0	31		465.0		0	0.0								

PROJECT NAME: **STATEWIDE-NORTH REGION**
PROJECT NUMBER: **STP HRRR(22)**
FILE NAME: **z14k100tsshydepark TH1 NB.** PLOT DATE: **5/5/2017**
PROJECT MANAGER: **K. RUTTER** DRAWN BY: **R. SHEDD**
DESIGNED BY: **R. SHEDD** CHECKED **S. GOODWIN**
HYDE PARK TH-1 NORTHBOUND 4 SHEET **120** OF **255**